

Location
Ridge to Bissel/Mayden
Safety Funding
90% Fed, 10% State
Y030 - 1E

Pay Item	Description	Unit	Total	Quantity
67100100	MOBILIZATION	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	3
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	3,614	3,614
81020700	CONDUIT PUSHED, 3" DIA., INTERMEDIATE METAL	FOOT	244	244
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	10,256	10,256
81603005	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	7,980	7,980
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	13,544	13,544
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	61	61
82500520	LIGHTING CONTROLLER TYPE CB - RCS 60AMP - 480VOLT	EACH	2	2
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1
83004600	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	EACH	61	61
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	61	61
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	196	196

Rev.

FILE NAME : c:\pwork\PMIDOT\LAUGHLINRL\dms76543\672C46-shr-500.dgn	USER NAME : laughlrrr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 668	SECTION 28L-1	COUNTY SANGAMON	TOTAL SHEETS 20	SHEET NO. 03
PLOT SCALE : 2.0000 ' / IN.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72C46		
PLOT DATE : Feb-05-2009 02:54:39PM	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT								