

STA/OFFSET	POLE ALUMINUM 50' MH 15' DAVIT ARM (EACH)	LIGHT POLE FOUNDATION 15" BOLT CIRCLE 8" x 8' (EACH)	LUMINAIRE SODIUM VAPOR HORIZ. MOUNT 400 WATT (EACH)	UNIT DUCT 2-1C NO. 8 1/C NO 8 GROUND (XLP-TY USE) 3/4" POLYETHYLENE (FOOT)	UNIT DUCT 2-1C NO. 10 1/C NO 10 GROUND (XLP-TY USE) 3/4" POLYETHYLENE (FOOT)	CONDUIT PUSHED, 2" DIA INTERMEDIATE METAL (FOOT)	CONDUIT PUSHED, 3" DIA INTERMEDIATE METAL (FOOT)	TRENCH AND BACKFILL FOR ELECTRICAL WORK (FOOT)
120+80	LIGHTING CONTROLLER #2 (SEE CONTROLLER SCHEDULE)			517	--	91	INCLUDED ABOVE	259
124+65 39' RT	1	1	1	325	--	153	--	162
127+80 35' RT	1	1	1	289	--	45	--	234
130+59 36' RT	1	1	1	270	--	37	--	223
133+19 38' RT	1	1	1	334	--	49	--	275
136+43 35' RT	1	1	1	365	--	--	--	355
139+98 35' RT	1	1	1	370	--	--	--	360
143+58 36' RT	1	1	1					
150+44 35' RT	1	1	1	--	370	--	--	360
154+04 35' RT	1	1	1	--	365	--	--	375
157+59 35' RT	1	1	1	--	305	--	--	295
160+54 35' RT	1	1	1	--	210	51	--	149
159+19 36' LT	1	1	1	--	160	16	--	134
160+59	LIGHTING CONTROLLER #3 (SEE CONTROLLER SCHEDULE)							
152+24 36' LT	1	1	1	--	370	--	--	360
155+84 35' LT	1	1	1	--	345	--	--	335
159+19 36' LT	INCLUDED ABOVE							
160+59	LIGHTING CONTROLLER #3 (SEE CONTROLLER SCHEDULE)			--	114	37	--	67
161+44 42' LT	1	1	1	--	275	42	--	223
164+09 44' LT	1	1	1	--	291	25	--	256
166+89 50' LT	1	1	1					
161+44 42' LT	INCLUDED ABOVE			--	210	59	--	141
162+69 39' RT	1	1	1	--	290	49	--	231
165+49 39' RT	1	1	1					
TOTALS	61	61	61	10256	7980	3614	244	13544

FILE NAME =	USER NAME = laughlrr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE				F.A.P. RTE. 668	SECTION 28L-1	COUNTY SANGAMON	TOTAL SHEETS 20	SHEET NO. 05
ct:\pw_work\PWIDOT\LAUGHLINRL\dms76543\672C46-sht-schedule.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72C46		
		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT								
		DATE -	REVISED -										