

100% F&D.

CONSTRUCTION TYPE CODE	
I-57	I-57
STA 841+07.00 TO STA 841+64.63	STA 900+52.80 TO STA 1386+91.00
STA. EQUATION: 841+64.63 (BK)= 813+20.49 (AH)	
STA 813+20.49 TO STA 900+52.80	
URBAN	RURAL

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	1000	1000
CODE NO	ITEM	UNIT			
<del>60100078</del>	<del>SHOULDER REMOVAL AND REPLACEMENT 12 1/2"</del>	<del>FOOT</del>	<del>18784</del>	<del>10346</del>	<del>8438</del>
60107600	PIPE UNDERDRAINS 4"	FOOT	222874	32129	190745
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	9155	1416	7739
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	8275	1975	6300
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	23	5	18
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4		4
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	8	4	4
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	10	2	8
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	6	2	4
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (FLARED)	EACH	39	9	30
* 63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2		2
63200310	GUARDRAIL REMOVAL	FOOT	10637.5	2512.5	8125
63400105	GUARD POSTS	EACH	50	10	40
63500105	DELINEATORS	EACH	279	37	242
64200105	SHOULDER RUMBLE STRIP	FOOT	215672	32743	182929
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18	4	14
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2		2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	2	2
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.15	0.85
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	0.15	0.85

100% F&D.

CONSTRUCTION TYPE CODE	
I-57	I-57
STA 841+07.00 TO STA 841+64.63	STA 900+52.80 TO STA 1386+91.00
STA. EQUATION: 841+64.63 (BK)= 813+20.49 (AH)	
STA 813+20.49 TO STA 900+52.80	
URBAN	RURAL

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	1000	1000
CODE NO	ITEM	UNIT			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	102485	17413.6	85071.4
<del>70300220</del>	<del>TEMPORARY PAVEMENT MARKING LINE 4"</del>	<del>FOOT</del>	<del>254902</del>	<del>37608</del>	<del>217294</del>
<del>70300250</del>	<del>TEMPORARY PAVEMENT MARKING LINE 8"</del>	<del>FOOT</del>	<del>1800</del>	<del>944</del>	<del>856</del>
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20,497	3,550	16,947
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2320		2320
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2320		2320
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	224,937	38,362	186,575
<del>78008310</del>	<del>POLYUREA PAVEMENT MARKING TYPE II LINE 4"</del>	<del>FOOT</del>	<del>221033</del>	<del>28148.3</del>	<del>192884.7</del>
<del>78008340</del>	<del>POLYUREA PAVEMENT MARKING TYPE II LINE 8"</del>	<del>FOOT</del>	<del>1800</del>	<del>944</del>	<del>856</del>
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2859	431	2428
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	176	44	132
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	45	11	34
X0301741	AERIAL SPEED CHECK MARKING	FOOT	72		72
X0322729	MATERIAL TRANSFER DEVICE	TON	69453	12184.1	57268.9
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	389	64	325
X6050700	REMOVE INLET BOX	EACH	3		3
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	14	14
XZ029997	REMOVE EXISTING ATTENUATOR BASE	SQ YD	298	60	238
Z0002005	ATTENUATOR BASE	SQ YD	508	101.6	406.4
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	10	2	8
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	10	2	8
Z0075300	TIE BARS	EACH	907	86	821

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			57	15(22,23,24,25,26)RS-3	COLES	87	5	
		CHECKED -	REVISED -			CONTRACT NO. 74158					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					