

PATCHING SCHEDULE

	CLASS A PATCHES, TYPE I, 8"	CLASS A PATCHES, TYPE II, 8"	CLASS A PATCHES, TYPE III, 8"	CLASS A PATCHES, TYPE IV, 8"	CLASS A PATCHES, TYPE IV, 10"	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	PAVEMENT PATCHING (PARTIAL DEPTH)	PATCHING REINFORCEMENT	SAW CUTS	TIE BARS
LOCATION	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	EACH
I-57 NB / SB	164.0	1973.0	462.0	324.0	3520.0	1980.0	1000.0	6500.0	24266.0	907.0
TOTALS	164.0	1,973.0	462.0	324.0	3,520.0	1,980.0	1,000.0	6,500.0	24,266.0	907.0

SEEDING SCHEDULE

	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING
LOCATION	ACRE	POUND	POUND	POUND	ACRE	POUND
SN 015-0049	0.5	46.8	46.8	46.8	0.5	52.0
SN 015-0048	0.5	44.1	44.1	44.1	0.5	49.0
SN 015-0044	0.5	42.3	42.3	42.3	0.5	47.0
SN 015-0046	0.6	56.7	56.7	56.7	0.6	63.0
SN 015-0033	0.4	35.1	35.1	35.1	0.4	39.0
PADS & SPBGR WIDENING	0.6	54.0	54.0	54.0	0.6	60.0
TOTALS	3.1	279.0	279.0	279.0	3.1	310.0

TEMPORARY CONCRETE BARRIER

	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
LOCATION	FOOT	FOOT
NB PL WORK AREA		
1277+87.70 TO 1279+37.70 NB	150.0	150.0
1279+37.70 TO 1283+67.70 NB	430.0	430.0
SB PL WORK AREA		
1279+37.70 TO 1283+67.70 SB	430.0	430.0
1283+67.70 TO 1285+17.70 SB	150.0	150.0
NB PL WORK AREA		
1383+26.00 TO 1384+76.00 NB	150.0	150.0
1384+76.00 TO 1389+06.03 NB	430.0	430.0
SB PL WORK AREA		
1384+76.00 TO 1389+06.00 SB	430.0	430.0
1389+06.03 TO 1390+56.00 SB	150.0	150.0
TOTALS	2,320.0	2,320.0

IMPACT ATTENUATOR SCHEDULE

	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	ATTENUATOR BASE	IMPACT ATTENUATOR REMOVAL	REMOVE EXISTING ATTENUATOR BASE	GUARD POSTS
LOCATION	EACH	SQ YD	EACH	SQ YD	EACH
SN 015-0049	2.0	101.6	2.0	59.6	10.0
SN 015-0048	2.0	101.6	2.0	59.6	10.0
SN 015-0044	2.0	101.6	2.0	59.6	10.0
SN 015-0046	2.0	101.6	2.0	59.6	10.0
SN 015-0033	2.0	101.6	2.0	59.6	10.0
TOTALS	10.0	508.0	10.0	298.0	50.0

DRAINAGE SCHEDULE

	PIPE CULVERTS, CLASS A, TYPE 1 24"	PIPE CULVERT REMOVAL	INLET BOX, STANDARD 542531	REMOVE INLET BOX	INLET & PIPE PROTECTION
LOCATION	FOOT	FOOT	EACH	EACH	EACH
SN 015-0048	52.0		1.0	1.0	1.0
SN 015-0046	43.0		1.0	1.0	1.0
SN 015-0033	35.0	25.0	1.0	1.0	1.0
TOTALS	130.0	25.0	3.0	3.0	3.0