

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS/LIST OF STANDARDS/GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTION
- 5 - 7 SCHEDULE OF QUANTITIES
- 8 - 14 TIE POINTS
- 15 - 29 PLAN AND PROFILE SHEETS
- 30 - 31 CRASHWALL MODIFICATION DETAILS
- 32 - 98 CROSS SECTIONS
- 99 -100 DETAIL SHEETS

LIST OF STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 001001-02 AREAS OF REINFORCEMENT BARS
- 001006 DECIMAL OF AN INCH AND OF A FOOT
- 280001-04 TEMPORARY EROSION CONTROL SYSTEMS
- 542531-03 INLET BOX TYPE G, 600mm (24")
- 542601-01 REINFORCED CONCRETE PIPE ELBOW
- 601001-03 SUB-SURFACE DRAINS
- 601101-01 CONCRETE HEADWALL FOR PIPE DRAIN
- 602601-02 PRECAST REINFORCED CONCRETE FLAT SLAB TOP
- 604001-03 FRAME AND LIDS, TYPE 1
- 630001-08 STEEL PLATE BEAM GUARD RAIL
- 630301-05 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARD RAIL TERMINALS
- 631011-05 TRAFFIC BARRIER TERMINAL, TYPE 2
- 635006-03 REFLECTOR AND TERMINAL MARKER PLACEMENT
- 635011-02 REFLECTOR MARKER AND MOUNTING DETAILS
- 701011-02 OFF-ROAD OPERATIONS, MULTILANE, 4.5m (15") TO 600mm (24") FROM PAVEMENT EDGE
- 701101-02 OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5m (15") AWAY
- 701400-03 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701406-05 LANE CLOSURE FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF ERECTING GUARDRAIL, PLACING EMBANKMENT, CONSTRUCTING IMPACT ATTENUATORS, CONSTRUCTING PIPE CULVERTS, INLETS, EXTENDING PIPE UNDERDRAINS (SPECIAL), AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

REMOVAL OF EXISTING GUARD POSTS IN THE AREAS OF THE CONSTRUCTION OF EMBANKMENTS SHALL BE CONSIDERED INCIDENTAL TO THE EARTH WORK.

ALL ELEVATIONS SHOWN IN PLANS ARE BASED ON U. S. G. S. DATUM.

ALL DISTURBED AREAS WITHIN THE CONSTRUCTION LIMITS SHALL BE FERTILIZED AND SEEDED. SEEDING SHALL BE CLASS 2 IN ACCORDANCE WITH THE SPECIAL PROVISIONS AND THE APPLICABLE ARTICLES OF SECTION 250 OF THE STANDARD SPECIFICATIONS.

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX - GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\pwidot\swartzw\dms50720\sh...	projects.74313.dgn	DRAWN -	REVISED -			70	D-7 SAFETY 2009-1	FAYETTE	100	2
PLOT SCALE = 20.0000' / IN.	CHECKED -	REVISED -	SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.							
PLOT DATE = 1/20/2009	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
						CONTRACT NO. 74313				