

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I-70 4 LANE FED 90% STATE 10%	I-70 4 LANE FED 90% STATE 10%	I-70 FED 90% STATE 10%
				SFTY-3J	SFTY-3N	SFTY-2A
20200100	EARTH EXCAVATION	CU YD	231		231	
20400800	FURNISHED EXCAVATION	CU YD	3506	271	3235	
25000200	SEEDING, CLASS 2	ACRE	6.9	0.4	6.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	623	38	585	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	623	38	585	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	623	38	585	
25100115	MULCH, METHOD 2	ACRE	6.9	0.4	6.5	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	692	42	650	
28000500	INLET AND PIPE PROTECTION	EACH	13		13	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	148	148		
50105220	PIPE CULVERT REMOVAL	FOOT	1139		1139	
50300225	CONCRETE STRUCTURES	CU YD	18.6			18.6
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1540			1540
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	1870		1870	
54205059	PIPE CULVERTS, SPECIAL 24"	FOOT	160		160	
54246405	INLET BOX, STANDARD 542531	EACH	13		13	
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	6		6	
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	71		71	
60260200	INLETS TO BE ADJUSTED (SPECIAL)	EACH	1		1	
60262900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1		1	
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	651	651		
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	3077	476.5	2600.5	
63400105	GUARD POSTS	EACH	120		120	
67100100	MOBILIZATION	L SUM	1		1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1		1	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
X0349800	CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL	EACH	6		6	
X6050700	REMOVE INLET BOX	EACH	6		6	
Z0002005	ATTENUATOR BASE	SQ YD	1219.2		1219.2	
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	2		2	
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	24		24	

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILEL#		DRAWN -	REVISED -					70	D-7 SAFETY 2009-1	FAYETTE	100	3
	PLOT SCALE = #SCALE#	CHECKED -	REVISED -		SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.			<b>CONTRACT NO. 74313</b>				
	PLOT DATE = #DATE#	DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				