SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			90% FED. 10% STATE	CONSTRUCTION TYPE CODE									
				EFFINGHAM COUNTY									
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY 3N LOCATION 1 SN 025-0054	SFTY 3N LOCATION 2 SN 025-0055	SFTY 3N LOCATION 3 SN 025-0057	SFTY 3J LOCATION 4 SN 025-0058	SFTY 3N LOCATION 5 SN 025-0059	SFTY 3N LOCATION 6 SN 025-0045	SFTY 3J LOCATION 7 SN 025-0062	SFTY 3J LOCATION 8 SN 025-0064	SFTY 3N LOCATION 9 SN 025-0051	SFTY 3N LOCATION 10 SN 025-0052
20200100	EARTH EXCAVATION	CU YD	76	9	15		11	11	13		3		14
20400800	FURNISHED EXCAVATION	CU YD	3805	440	420	338	285	182	215	504	555	525	341
25000200	SEEDING, CLASS 2	ACRE	4.08	0.38	0.57	0.4	0.4	0.41	0.45	0.56	0.42	0.09	0.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	367	35	51	36	36	37	40	50	38	8	36
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	367	35	51	36	36	37	40	50	38	8	36
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	367	35	51	36	36	37	40	50	38	8	36
25002300	TEMPORARY SEEDING	ACRE	4.08	0.38	0.57	0.4	0.4	0.41	0.45	0.56	0.42	0.09	0.4
25100115	MULCH, METHOD 2	ACRE	4.08	0.38	0.57	0.4	0.4	0.41	0.45	0.56	0.42	0.09	0.4
28000300	TEMPORARY DITCH CHECKS	EACH	22	2	4	2	2	2	2	2	2	2	2
28000500	INLET AND PIPE PROTECTION	EACH	15	2		2	2	1	1	1	2	2	2
50105220	PIPE CULVERT REMOVAL	FOOT	2551	49	271	271	269	270	269	508	325	266	53
54200433	PIPE CULVERTS, TYPE 1 RCCP 18"	FOOT	1485				309	363	305	508			
54200439	PIPE CULVERTS, TYPE 1 RCCP 24"	FOOT	1252	154		309					309	307	173
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	6					2	2	2			
54246205	INLET BOX, STANDARD 542526	EACH	9	2		2					2	2	1
60260100	INLETS TO BE ADJUSTED	EACH	1										1
60500060	REMOVING INLETS	EACH	3	2									1
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	50							50			
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2							2			
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2							2			
63200310	GUARDRAIL REMOVAL	FOOT	2740	202	228	227	226	228	227	711	236	227	228
63400105	GUARD POSTS	EACH	100	10	10	10	10	10	10	10	10	10	10
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3
67100100	MOBILIZATION	L SUM	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4							4			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4							4			
Z0030150	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	20	2	2	2	2	2	2	2	2	2	2