CONTRACT NO. 76709

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 - 1A I-70 & FRONTAGE RD 100% FED	I000 - 1A IL 162 ROADWAY 100% FED	I000 - 1A I-70 & FRONTAGE RD ROADWAY 100% FED	I000 - 1A IL 162 ROADWAY 100% FED	I000 - 1A IL 162 @ RAMPS & EAST FRONT. RD TRAFFIC SIGNALS 100% FED	I000 - 1A IL 162 @ WEST FRONT. RD TRAFFIC SIGNALS 100% FED	X771-2A BRIDGE REPLACEMENT 100% FED	I000 - 1A MSE WALLS 100% FED	I000 - 1A SIGNING 100% FED	I000 - 1A I-55/70 HIGHWAY LIGHTING 100% FED	I000 - 1A IL 162 HIGHWAY LIGHTING 100% FED
* 83502350	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 5	EACH	2										2	
X0326371	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 27"	FOOT	190	190										
X0326377	HIGH LOAD MULTI-ROTATION BEARINGS, NON-GUIDED EXPANSION, 50K	EACH	8							8				
X0326378	HIGH LOAD MULTI-ROTATION BEARINGS, NON-GUIDED EXPANSION, 75K	EACH	6							6				
X0326379	HIGH LOAD MULTI-ROTATION BEARINGS, NON-GUIDED EXPANSION, 100K	EACH	6							6				
X0326380	HIGH LOAD MULTI-ROTATION BEARINGS, NON-GUIDED EXPANSION, 150K	EACH	6							6				
X0326381	HIGH LOAD MULTI-ROTATION BEARINGS, NON-GUIDED EXPANSION, 200K	EACH	4							4				
~~X0326376~~ X0326442	~~STONE COLUMNS~~ AGGREGATE COLUMN GROUND IMPROVEMENT	~~FOOT~~ CU YD	~~31800~~ 8325								~~31800~~ 8325			
X0326375	PRECAST CONCRETE BOX CULVERT END SECTIONS 6' X 4'	EACH	1		1									
X0326374	GRATING FOR BOX CULVERT 6' X 4'	EACH	1				1							
X0326373	GRATING FOR BOX CULVERT 5' X 2'	EACH	1				1							
X0326372	REMOVE RIGHT OF WAY MARKERS	EACH	13	13										
XX003565	SEEDING SPECIAL, COMPLETE	ACRE	8.75			8.75								
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	32400								32400			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	864	328		340	196							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	72	57		15								
20101100	TREE TRUNK PROTECTION	EACH	10	10										
20200100	EARTH EXCAVATION	CU YD	151868	73761	2149	44635	31323							
20400100	BORROW EXCAVATION	CU YD	88055			29109	58946							
20800150	TRENCH BACKFILL	CU YD	1457	96		1087	274							
25000115	SEEDING, CLASS 1B	ACRE	1				1							
25000200	SEEDING, CLASS 2	ACRE	17.25	7.6	2.57	2.87	4.21							
25000210	SEEDING, CLASS 2A	ACRE	9.25			9.25								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3263	684	231	1879	469							
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3263	684	231	1879	469							
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3263	684	231	1879	469							
25000700	AGRICULTURAL GROUND LIMESTONE	TON	72.5	15.2	5.14	41.74	10.42							
25100115	MULCH, METHOD 2	ACRE	36.25	7.6	2.57	20.87	5.21							
25100630	EROSION CONTROL BLANKET	SQ YD	820	820										

*Specialty Items

PLOT DATE = 2/10/2009
FILE NAME = c:\pw_work\PWIDOT\KEPLARCL\dms88415\pl-00003a.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = KHEF4