

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

I000-1A

X771-2A

I000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3625	1812.5	1812.5										
28000300	TEMPORARY DITCH CHECKS	EACH	114	30	23	58	3								
28000400	PERIMETER EROSION BARRIER	FOOT	4258	2765	1292	201									
28000500	INLET AND PIPE PROTECTION	EACH	93	41	2	30	20								
28100127	STONE RIPRAP, CLASS B4	SQ YD	400	17		383									
28200200	FILTER FABRIC	SQ YD	400	17		383									
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	111109	35162	6531	44197	25219								
30201500	LIME	TON	1974	674	125	692	483								
31200100	STABILIZED SUB-BASE 4"	SQ YD	50289			26030	24259								
35100100	AGGREGATE BASE COURSE, TYPE A	TON	957	330	99	490	38								
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	2482			96	2386								
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	193	77			116								
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	1342	981			361								
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	7000	7000											
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17.6	11.8	5.8										
40600300	AGGREGATE (PRIME COAT)	TON	140.4	92.4	48										
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	128	128											
40600895	CONSTRUCTING TEST STRIP	EACH	5	3	2										
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	174		174										
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	1117		1117										
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	916			916									
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	9572	9572											
40701891	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10 1/2"	SQ YD	2042	2042											
40701906	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 1/4"	SQ YD	3947	3947											
40701916	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 11 3/4"	SQ YD	6186	6186											
40701951	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/2"	SQ YD	7918	7918											
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	2510	2510											
40701976	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 3/4"	SQ YD	5119	5119											
40701991	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 1/2"	SQ YD	4327	4327											