

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

I 000-1A

X771-2A

I 000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT		4251		4251									
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		680	197	289	194								
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10						10						
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	36		30	6									
78200300	PRISMATIC CURB REFLECTOR	EACH	279			279									
78200305	PRISMATIC BARRIER REFLECTOR	EACH	34		26	8									
78200410	GUARDRAIL MARKERS, TYPE A	EACH	24		24										
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6		6										
80300100	LOCATING UNDERGROUND CABLE	FOOT	6000			5000							1000		
80400100	ELECTRIC SERVICE INSTALLATION	EACH	4									2	2		
80500100	SERVICE INSTALLATION, TYPE A	EACH	3				2	1							
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	198									86	112		
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	754				580	174							
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	2279				1764	515							
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	156				100	56							
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	138				138								
81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	320				320								
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	541				340	201							
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	990				101					252	637		
81018800	CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	161				161								
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1119				455	307				357			
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	479									479			
81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	95									95			
81101000	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL	FOOT	583				583								
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	10									10			
81300945	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 8"	EACH	2									2			
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	27				17	8				2			
81400705	HANDHOLE, PORTLAND CEMENT CONCRETE (SPECIAL)	EACH	2				2								

*Specialty Items

PLOT DATE = 2/16/2009
 PLOT SCALE = 1/8" = 1'-0"
 REFERENCE = #REF#