CONTRACT NO. 76709

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	12
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-1A						X771-2A	I000-1A			
				I-70 & FRONTAGE RD	IL 162	I-70 & FRONTAGE RD	IL 162	IL 162 @ RAMPS & EAST FRONT. RD	IL 162 @ WEST FRONT. RD				I-55/70	IL 162
				ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5					4	1					
81603010	UNIT DUCT, 600V, 2-1C NO. 10, 1/C NO. 10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	95										95	
81603025	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	18419										18419	
81603035	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	5220											5220
81701125	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 1/C NO. 1/0	FOOT	691										306	385
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1447										1447	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	24426					2910	737				16246	4533
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	116										87	29
82105700	LUMINAIRE, SODIUM VAPOR, HIGH MAST, HORIZONTAL MOUNT, 750 WATT	EACH	16										16	
82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	10										10	
82109200	SIGN LIGHTING LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM	EACH	5										5	
* 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240 VOLT	EACH	2											2
82500540	LIGHTING CONTROLLER TYPE CB-RCS 100AMP - 480VOLT	EACH	2										2	
83024500	LIGHT POLE, ALUMINUM, TRANSFORMER BASE 50 FT. M.H., 12 FT. MAST ARM	EACH	116										87	29
83503200	LIGHT TOWER, 110 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 3	EACH	2										2	
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	812										609	203
83700100	LIGHT TOWER FOUNDATION	FOOT	72										72	
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	15										15	
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1											1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1											1
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2					1	1					
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1					1						
86000100	MASTER CONTROLLER	EACH	1					1						
84200802	POLE FOUNDATION REMOVE	EACH	15										15	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1											1

*Specialty Items

Rev.

PLOT DATE = 2/10/2009
FILE NAME = c:\pw_work\PWIDOT\KEPLARCL\dms89415\sjln88083a.dgn
PLOT SCALE = 50.000 ' / IN.
REFERENCE = REF