

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	60-10K-1, 60-10HB	MADISON	420	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

I 000-1A

X771-2A

I 000-1A

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			TOTAL QUANTITIES	I-70 & FRONTAGE RD		I-70 & FRONTAGE RD		IL 162 e RAMP & EAST FRONT. RD		IL 162 e WEST FRONT. RD		I-55/70		IL 162	
CODE NO	ITEM	UNIT		ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	ROADWAY 100% FED	TRAFFIC SIGNALS 100% FED	TRAFFIC SIGNALS 100% FED	BRIDGE REPLACEMENT 100% FED	MSE WALLS 100% FED	SIGNING 100% FED	HIGHWAY LIGHTING 100% FED	HIGHWAY LIGHTING 100% FED	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9					9							
X0301183	GEOMETRICALLY PROGRAMMED LOUVER	EACH	4					4							
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	2750			2750									
X0321760	DOUBLE HANDHOLE REMOVAL	EACH	2					2							
X0323149	TEMPORARY MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	1600							1600					
X0323236	TEMPORARY INLET	EACH	5	5											
X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	35					35							
X0323383	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 18"	FOOT	18		18										
X0323429	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 21"	FOOT	112		112										
X0323430	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 24"	FOOT	110		110										
X0323670	PREFORMED DETECTOR LOOP	FOOT	8342					6022	2320						
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	4							4					
X0324548	PRECAST CONCRETE BOX CULVERT END SECTIONS 6' X 3'	EACH	1					1							
X0324567	RELOCATE MOTORIST AID CALL BOX	EACH	1		1										
X0325618	HIGH LOAD MULTI-ROTATION BEARINGS, FIXED - 250K	EACH	13							13					
X0325638	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 100K	EACH	26							26					
X0325643	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 350K	EACH	2							2					
X0325648	HIGH LOAD MULTI-ROTATION BEARINGS, GUIDED EXPANSION, 650K	EACH	2							2					
X0336850	PRECAST CONCRETE BOX CULVERT END SECTIONS 5' X 2'	EACH	1					1							
X0545000	BOX CULVERT REMOVAL	FOOT	33					33							
X0728700	GRATING FOR BOX CULVERT 6' X 3'	EACH	1					1							
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	6					6							
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	6					6							
X6050700	REMOVE INLET BOX	EACH	4		4										
*X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	103.5								103.5				
*X7800450	POLYUREA PAVEMENT MARKING TYPE I - CURB	FOOT	1226					1226							
*X7800500	POLYUREA PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ FT	967		593			374							
*X7800510	POLYUREA PAVEMENT MARKING SPECIAL - LINE 4"	FOOT	610					610							

* Specialty Items

PLOT DATE: 2/10/2009
 PLOT SCALE: 50,000 / 1" = 1000'
 PLOT REFERENCE: REF#