

FIL ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	MADISON	420	24

STA. _____ TO STA. _____
 CONTRACT NO.: 76709
 * 60-10K-1, 60-10HB

STORM SEWER AND PIPE CULVERT SCHEDULE

Location	Structure No.	PRECAST CONCRETE BOX CULVERT		STORM SEWERS, TYPE 1		PIPE CULVERTS, TYPE 1 RCCP										PIPE CULVERTS, TYPE 2 RCCP		PIPE CULVERTS, TYPE 3 RCCP		PIPE CULVERTS, TYPE 4 RCCP		PIPE CULVERTS, CLA. 24" (JACKED)	TRENCH BACKFILL
		6' x 4'	5' x 2'	12"	12" Watermain Requirement	15"	18"	18" Watermain Requirement	21"	21" Watermain Requirement	24"	24" Watermain Requirement	27"	27" Watermain Requirement	36"	24"	24"	15"	24"	L.F.	CU. YD.		
IL Route 162		L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	CU. YD.	
479+60.75						57																0	
484+04.50		8																				0	
485+22.05 TO 485+61.00	1R TO 2R																					5.9	
485+85.27 TO 486+19.23	3R TO 4R					34																4.4	
490+80.00	7R				35																	0	
492+80.00	8R			14																		0	
485+60.45 TO 486+11.51	1L TO 2L					51																9.6	
492+80.00	3L			15																		0	
495+20.00	4L			11																		0	
497+30 TO 498+15	5L TO 6L			100																		18.6	
496+53.00				140																		38.8	
501+35 TO 502+25	7L TO 8L			102																		19.0	
502+25 TO 502+80				115																		35.0	
504+00 TO 506+00	9L TO 10L			197																		0	
506+00.00				55																		0	
494+80.00	9R			75																		0	
497+00 TO 497+60	10R TO 11R			135																		13.9	
496+44.6 TO 497+00				76																		37.3	
500+80 TO 501+55	12R TO 13R			100																		21.0	
501+55 TO 502+46				141																		70.4	
504+20 TO 505+75	14R TO 15R			153																		0	
505+71.90				59																		0	
495+87.00		74																				0	
East Frontage Road																						0	
51+40.70						5 (*)																0	
50+70.20						10 (*)																0	
43+00 TO 42+98.60											110											10.6	
41+12 TO 40+53																						11.0	
37+45.70																						0	
36+40.00				4																		0	
36+21.80				6																		0	
35+83.4 TO 37+45.7																						19.9	
34+13.5 TO 33+64.2																						45.8	
33+56 TO 33+17.8					42			135														8.7	
21+06.60															32							0	
21+30.50																						0	
21+10.2 TO 21+00.5																						0	
15+05.4 TO 14+95.4																						0	
14+98.20																						0	
14+95.2 TO 14+85.2																						0	
West Frontage Road																						5.5	
22+48.4 TO 23+03.4									110													0	
23+42.8 TO 23+54.35										112												0	
23+58.2 TO 23+60.0				10																		0	
23+99.4 TO 24+00.0				13																		8.4	
23+50.9 TO 24+10.5																						0	
26+30 TO 27+00								130			108											0	
27+38.00										18												0	
26+10.00										5												0	
26+63.00										5												0	
24+37.4 TO 24+74.7						90																0	
Ramp A																						188	
17+50 TO 19+40																						198	
17+50 TO 19+50																						103	
19+40 TO 20+50																						111	
19+50 TO 20+47																						381	
20+44 TO 20+91																						295.2	
21+00.00				33																		0	
22+50.00				52																		0	
Ramp B																						112	
15+03.74 TO 15+17																						119.2	
14+34.00																						0	
13+00.00																						0	
Ramp C																						0	
24+50.00						43																184	
25+30.8 TO 25+52.4																						262.9	
Ramp D																						507	
12+34 TO 12+56.3																						395.8	
13+00.00																						0	
14+42.00																						0	
I-55/70																						144	
1347+68 LT TO RT																						0	
1347+67.4 TO 1347+77.4																						0	
1355+91.3 TO 1356+01.3																						0	
1356+01.3 LT TO RT																						459	
1356+01.3 TO 1356+11.3																						0	
TOTAL =		8	74	1829	35	313	408	18	218	112	66	110	600	190	32	381	112	184	507	603	1457		

(* DENOTES METAL PIPE)

PIPE CULVERT REMOVAL

LOCATION		PIPE CULVERT REMOVAL 12" * (FEET)	PIPE CULVERT REMOVAL 18" * (FEET)	PIPE CULVERT REMOVAL 24" * (FEET)	PIPE CULVERT REMOVAL 30" * (FEET)	PIPE CULVERT REMOVAL 23"x14" * (FEET)	BOX CULVERT REMOVAL 6' x 3' (FEET)
IL ROUTE 162							
479+60.75	LT TO 479+60.75 RT	42					
493+46.60	TO						33
I-55/70							
1352+28.00				28			
1352+12.00				27			
1354+01							