

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS,  
GENERAL NOTES AND COMMITMENTS
- 3-4 SUMMARY OF QUANTITIES
- 5-6 TYPICAL SECTIONS
- 7 SCHEDULES OF QUANTITY
- 8 TIE POINTS & BENCH MARKS
- 9-12 PLAN AND PROFILE SHEETS
- 13 WIDE LOAD SIGN PLAN
- 14-19 STAGE CONSTRUCTION SHEET
- 20-22 EROSION CONTROL SHEET
- 23-26 PLAT OF HIGHWAYS
- 27-29 PAVEMENT MARKING SHEETS
- 30-66 BRIDGE PLANS
- 67 MISCELLANEOUS DETAILS
- 68-75 MAINLINE CROSS SECTIONS
- 75A, -75D BRIDGE APP. PAV'T. DETAILS*

HIGHWAY STANDARDS

000001-05	630001-08	701301-03
001001-02	630301-05	701311-03
001006	631031-07	701321-10
202001-01	635006-03	701326-03
280001-04	635011-02	701901-01
420401-07	666001-01	704001-05
482001-02	667001-01	780001-02
515001-03	667101-01	781001-03
	<i>601101-01</i>	

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
  2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
  3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO ALL UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
    - AMERENCIPS (ELECTRIC)
    - AMERENCIPS (GAS & ELECTRIC)
    - VILLAGE OF GODFREY (WATER)
    - ILLINOIS AMERICAN WATER COMPANY (WATER)
    - JERSEY COUNTY RURAL WATER COMPANY (WATER)
    - AT&T ILLINOIS (COMMUNICATIONS)
- MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY \*.  
NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE MINIMAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
  5. NO OPEN TRENCHES SHALL BE PERMITTED DURING WINTER SHUTDOWN OR AS DIRECTED BY THE ENGINEER.
  6. THE CONTRACTOR SHALL SAWCUT ALONG THE EDGE OF THE ROADWAY PRIOR TO PLACING THE WIDENING FOR STAGE CONSTRUCTION AS DETAILED IN THE PLANS. THE COST SHALL BE INCLUDED IN THE COST OF THE REMOVAL ITEM.
  7. RIGHT-OF-WAY MARKERS SHALL BE SET SO THE BACK OF THE POST IS TWELVE INCHES (12") INSIDE THE RIGHT OF WAY BOUNDARY. RIGHT OF WAY PROPERTY CORNERS ARE MARKED BY A 5/8" IRON ROD WITH IDOT ALUMINUM CAP AND SHALL NOT BE REMOVED OR DAMAGED WHEN SETTING THE RIGHT OF WAY MARKERS.
  8. BRIDGE APPROACH PAVEMENT IS INCLUDED IN PAVEMENT REMOVAL.

TRAFFIC CONTROL NOTES:

1. THE CONTRACTOR SHALL FURNISH AND INSTALL WOOD SIGN SUPPORTS IN ACCORDANCE WITH SECTION 730 OF THE STANDARD SPECIFICATIONS.
2. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT EACH END OF THE PROJECT, AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLOURESCENT ORANGE (48").
3. ALL EXCAVATION ADJACENT TO THE EDGE OF PAVEMENT SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND APPROPRIATE LIGHTS.
4. THE BOTTOM 6" OF TEMPORARY CONCRETE BARRIER SHALL BE PAINTED WHITE. A QUANTITY OF 562.5 FT SHALL BE PAID FOR AS "TEMPORARY PAVEMENT MARKING - LINE 6" ".

COMMITMENTS

WETLAND SHALL BE STAKED PRIOR TO CONSTRUCTION SO THAT NO IMPACT TO WETLAND IS ASSURED. ENVIRONMENTAL UNIT (JENNIFER HUNT: 618-346-3156) SHOULD BE INFORMED WHEN STAKING IS TAKING PLACE.

FILE NAME =	USER NAME = herbaughrd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pw_work\pwsdot\herbaughrd\dms52127\p	02186a.dgn	DRAWN -	REVISED -			8956	59BR-1	MADISON	75	2
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			<b>CONTRACT NO. 76B18</b>				
	PLOT DATE = 3/16/2009	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.

Rev.