

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		100% STATE I000-2A	50% CITY 50% STATE I000-2A	100% CITY I000-2A	CODE NO	ITEM	UNIT		100% STATE I000-2A	50% CITY 50% STATE I000-2A	100% CITY I000-2A
20200100	EARTH EXCAVATION	CU YD	620	620		550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	41	41			
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5		550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	83	83			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45		550A0220	STORM SEWERS, CLASS A, TYPE 1 66"	FOOT	43	43			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45		550A2420	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 48"	FOOT	108	108			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45		55101900	STORM SEWER REMOVAL 48"	FOOT	19	19			
25100120	MULCH, METHOD 2	TON	1	1		55102500	STORM SEWER REMOVAL 84"	FOOT	42	42			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40	40		60100965	PIPE DRAINS 18"	FOOT	5	5			
28000400	PERIMETER EROSION BARRIER	FOOT	308	308		60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
28000500	INLET AND PIPE PROTECTION	EACH	16	16		60247800	JUNCTION CHAMBER	EACH	1	1			
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1215	1215		60262800	INLETS TO BE RECONSTRUCTED (SPECIAL)	EACH	2	2			
35501328	HOT-MIX ASPHALT BASE COURSE, 11"	SQ YD	762	762		60266600	VALVE BOXES TO BE ADJUSTED	EACH	15		15		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	36	36		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	16		16		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	49.9	36.6	13.3	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1261.5	1261.5			
40600300	AGGREGATE (PRIME COAT)	TON	80	59	21	63200310	GUARDRAIL REMOVAL	FOOT	28	28			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1129	989	140	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		67100100	MOBILIZATION	L SUM	1	1			
40600990	TEMPORARY RAMP	SQ YD	429	429		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2769	1981	788	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	41	41		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
42001300	PROTECTIVE COAT	SQ YD	590	590		70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	28	28			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	31,123	22577	8546	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5193	5193			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	131	131		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	656	656			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	796	796		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21840	21840			
44004250	PAVED SHOULDER REMOVAL	SQ YD	542	542		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3140	3140			
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SQ YD	10	10		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	675	675			
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	204	204		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10614	10614			
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	65	65		*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	656	656			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1199	1199		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21840	21840			
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1		*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3140	3140			
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1		*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	675	675			
54215553	METAL END SECTIONS 18"	EACH	1	1									
54216003	REINFORCED CONCRETE PIPE ELBOW 48"	EACH	2	2									
55039700	STORM SEWERS TO BE CLEANED	FOOT	382	382									

*\* Specialty Items*

FILE NAME =	USER NAME = conoverpj	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\p\work\PWIDOT\CONOVERPJ\dms66862.d	76c35-shr-plan.dgn	DRAWN - ---	REVISED - ---			690	41X-RS-1	MADISON	58	4	
	PLOT SCALE = 50.0000' / IN.	CHECKED - ---	REVISED - ---			CONTRACT NO. 76C35					
	PLOT DATE = 1/15/2009	DATE - ---	REVISED - ---			SCALE: _____ SHEET NO. 1 OF 2 SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT	