

AP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	220	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES US 45 - IL 13 RELOCATION - CONTRACT 6		COUNTY:		SALINE			
		LOCATION:		URBAN			
CONSTRUCTION TYPE CODE:		FUNDING: 100% FED.		1000-2A	X081-2A	X028-2A	Y031-1F
CODE NUMBER		UNIT	TOTAL QUANTITY	ROAD FOUR LANE	BRIDGE SN 083-0060	BRIDGE SN 083-2020	TRAFFIC SIGNAL
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	140	140			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	5	5			
70300520	PAVEMENT MARKING TAPE - TYPE III, 4"	FOOT	26,910	26,910			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	26,910	26,910			
70500615	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	2	2			
72000100	SIGN PANEL, TYPE 1	SQ FT	285	256			9
72400320	REMOVE SIGN PANEL - TYPE 2	SQFT	512	512			
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	256	256			
78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS & SYMBOLS	SQ FT	582	582			
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	76,120	76,120			
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	2,821	2,821			
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	840	840			
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	3,909	3,909			
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	165	165			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	562	562			
78200405	GUARDRAIL MARKERS	EACH	7	7			
78200500	BARRIER WALL MARKERS	EACH	214	214			
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	4	4			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	562	562			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	165	165			
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	205				205
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	144	144			
81500100	GULFBOX JUNCTION	EACH	2				2
81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	255	255			
81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	270	270			
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	730	525			205
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	2	2			
83000190	LIGHT POLE, ALUMINUM, 25 FT. M.H., 6 FT. DAVIT ARM	EACH	2	2			
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	22	22			
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	5	5			
84200700	LIGHTING FOUNDATION REMOVAL	EACH	5	5			
87301305	ELECTRIC CABLE IN CONDUIT LEAD-IN, NO. 14, 1 PAIR	FOOT	700				700
88040070	SIGNAL HEAD, POLYCARBONATE LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1				1
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2				2
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1				1
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	2				2
88500100	INDUCTIVE LOOP DETECTOR	EACH	3				3
88500200	INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT	EACH	1				1
88600100	DETECTOR LOOP, TYPE 1	FOOT	461				461
89502200	MODIFY EXISTING CONTROLLER	EACH	1				1

*Specialty Items

CHECKED BY: BWM PLOT DATE: 2/4/2009
 DRAWN BY: DMS PLOT SCALE: 1/4"=1'-0"

M:\PROJECTS\PROJECTS\ROADWAY\COMMON\Reference Files\SUM04-3526.cgm
 Active File: SUM04-3526.cgm