

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	220	20
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TREE REMOVAL

STATION	OFFSET		STA. DIFF. FT.	AREA LT. SQ. FT.	AREA RT. SQ. FT.
	LEFT	RIGHT			
IL 13 RELOCATION					
973+20	166	0	80	11240	0
974+00	115	0	100	12000	2900
975+00	125	58	100	12700	2900
976+00	129	0	100	12500	5250
977+00	121	105	100	12250	10900
978+00	124	113	100	12200	11350
979+00	120	114	100	11350	11700
980+00	107	120	100	10600	11000
981+00	105	100	100	10550	10500
982+00	106	110	100	10600	8500
983+00	106	60	100	8350	11250
984+00	61	165	100	4050	16250
985+00	20	160	100	1850	16000
986+00	17	160	100	1100	15750
987+00	5	155	100	250	16450
988+00	0	174	100	0	10450
989+00	0	35	100	0	3750
990+00	0	40	100	0	8750
991+00	0	135	100	250	13750

STATION	OFFSET		STA. DIFF. FT.	AREA LT. SQ. FT.	AREA RT. SQ. FT.
	LEFT	RIGHT			
992+00	5	140	100	500	10750
993+00	5	75	100	750	3750
994+00	10	0	100	1000	4000
995+00	10	80	100	1750	6000
996+00	25	40	100	2500	3500
997+00	25	30	100	2750	3100
998+00	30	32	100	3500	3350
999+00	40	35	100	5000	3250
1000+00	60	30	100	5200	3300
1001+00	44	36	100	4350	3800
1002+00	43	40	100	5450	4000
1003+00	66	40	100	5700	3500
1004+00	48	30	100	4700	3400
1005+00	46	38	100	4400	4650
1006+00	42	55	100	5950	5350
1007+00	77	52	100	7100	5650
1008+00	65	61	99	5445	6039
1008+99	45	61	1	45	102
1009+00	45	143	100	4750	14250

STATION	OFFSET		STA. DIFF. FT.	AREA LT. SQ. FT.	AREA RT. SQ. FT.
	LEFT	RIGHT			
1010+00	50	142	100	5850	14100
1011+00	67	140	100	6850	10000
1012+00	70	60	100	7500	4000
1013+00	80	20	50	4000	1000
1013+50	80	20	50	3750	1125
1014+00	70	25	100	6000	3500
1015+00	50	45	100	4500	4500
1016+00	40	45	100	4000	4750
1017+00	40	50	100	3850	5250
1018+00	37	55	100	3750	5750
1019+00	38	60	100	3650	6000
1020+00	35	60	99	3465	5940
1020+99	35	60	1	35	84
1021+00	35	108	100	3250	10300
1022+00	30	98	100	2500	9850
1023+00	20	99	50	875	4925
1023+50	15	98			
TOTAL (Sq. Ft.)				266505	370215
TOTAL (Acres)				14.62	

STATION	OFFSET		6 TO 15 IN. UNIT	OVER 15 IN. UNIT	REMARKS
	LEFT	RIGHT			
OLD IL 13					
988+69		30		36	
989+36	26			59	
990+26	16			24.5	
991+02		38		19.6	
991+10		34		18.5	
991+50	56			33.7	
991+68	1	25		22.1	
991+95				41.3	
992+00	54			36.5	
994+00	31			15.8	
994+55	47			24	
994+85	20			22.3	
996+95	21			20.6	
1000+10	48		11.2		SPLIT TREE
1000+10	48		13.3		SPLIT TREE
1002+14		4	13.1		
1002+27	17		11		
1002+65		57	12.3		
IL 13 RELOCATION					
969+50	95		8.1		
969+75	39			30.4	
970+00	108			15.6	
970+00	108		6		
970+00	110		9		
970+35		24		16	
Total	Units		84	435.9	

STATION	OFFSET		STA. DIFF. FT.	AREA LT. SQ. FT.	AREA RT. SQ. FT.
	LEFT	RIGHT			
IL 13 RELOCATION					
1079+20	0	99	80	0	7960
1080+00	0	100	98	0	10094
1080+98	0	106	2	96	212
1081+00	96	106	50	5075	5150
1081+50	107	100	1	53.5	50
1081+51	0	0			
TOTAL (Sq. Ft.)				5224.5	23466
TOTAL (Acres)				0.66	

CHECKED BY: BUN PLOT DATE 2/1/2009
DRAWN BY: DMS PLOT SCALE 1:62500

M:\PROJECTS\PROJECTS\ROADWAY\COMMON\Reference Files\SCH001-352606.dgn