

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION TYPE CODE	
		UNIT	URBAN TOTAL QUANTITIES 80% FED 20% STATE
X4200830	PORTLAND CEMENT CONCRETE INLAY, 3"	SQ YD	108
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	731
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SQ YD	731
40600115	POLYMERIZED BITUMINOUS MATERIALS(PRIME COAT)	GALLON	5204
40600300	AGGREGATE (PRIME COAT)	TON	87
40600990	TEMPORARY RAMP	SQ YD	425
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	4857
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	57651
44003700	MEDIAN REMOVAL (SPECIAL)	SQ FT	6576
44201361	CLASS C PATCHES, TYPE I, 11 INCH	SQ YD	72
44201365	CLASS C PATCHES, TYPE II, 11 INCH	SQ YD	1222
44201369	CLASS C PATCHES, TYPE III, 11 INCH	SQ YD	383
44201371	CLASS C PATCHES, TYPE IV, 11 INCH	SQ YD	598
44213200	SAW CUTS	FOOT	719
60622700	CONCRETE MEDIAN TYPE SM-6.06 (SPECIAL)	SQ FT	34
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2
67100100	MOBILIZATION	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	1.3
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4492
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	773
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38998