

## SUMMARY OF QUANTITIES (CONTINUED)

CODE NO.	ITEM	CONSTRUCTION TYPE CODE	
		UNIT	I000 <i>URBAN</i> TOTAL QUANTITIES 80% FED 20% STATE
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	365
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	145
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	422
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16548
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	775
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38480
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	365
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	76
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	288
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	106
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	518
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	69
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	134
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	464
78300100	PAVEMENT MARKING REMOVAL	SQ FT	615
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	464
* 88600100	DETECTOR LOOP, TYPE I	FOOT	877

*\*specialty items*

FILE NAME =	USER NAME = noasdp	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw_work\PI\1001\NAASDP\dms43722\s97872_sht.sch.dgn		DRAWN -	REVISED -			885	104RS-5, 13RS-1, 106RS-4	UNION	24	4	
PLOT SCALE = 32.4256' / IN.		CHECKED -	REVISED -			CONTRACT NO. 78072					
PLOT DATE = 1/21/2009		DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	