



- NOTES:**
- THE PLANS SHOW THE LOCATION OF CERTAIN UNDERGROUND AND OVERHEAD UTILITY LINES, WATER MAINS, GAS MAINS, COMMUNICATIONS LINES, SEWERS, ETC. EVERY POSSIBLE MEANS HAS BEEN EMPLOYED TO RESEARCH AND FIELD LOCATE THESE FACILITIES INCLUDING ON-SITE EXPLORATION, JULI, I.E. LOCATORS, VILLAGE OF WINFIELD RECORDS, NICOR, AT&T AND COMMONWEALTH EDISON. THE LOCATION OF THE FIBER OPTIC CABLE WAS VERIFIED AT FIELD MEETINGS WITH SPRINT CABLE REPRESENTATIVES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER PROTECTION FROM DAMAGE TO THESE AND ANY UNFORESEEN FACILITIES DURING ALL PHASES OF CONSTRUCTION.
 - IT SHALL BE THE CONTRACTORS' RESPONSIBILITY TO CONTACT ANY AND ALL PRIVATE UTILITY OWNERS IN ADVANCE TO LOCATE AND COORDINATE ANY RELOCATION OF ANY UTILITY THAT MAY BE AFFECTED BY HIS WORK. ALL REQUISITE COORDINATION EFFORT AND DELAY NECESSARY TO RELOCATE UTILITIES SHALL BE CONSIDERED THE CONTRACTOR'S RESPONSIBILITY AND SHALL BE CONSIDERED INCIDENTAL TO THE COST OF THE CONTRACT. SEE SPECIAL PROVISIONS FOR MORE REQUIREMENTS.
 - FOR ANY AND ALL DEMOLITION AND / OR RELOCATION OF ANY ELECTRICAL CONDUIT AND FEEDS, SITE LIGHTING, COMMUNICATION CABLES AND APPURTENANCES FOR THESE UTILITIES, REFER TO THE ELECTRICAL AND PLANS PREPARED BY POWRTEK ENGINEERING.
 - ANY AND ALL DEMOLITION AND / OR RELOCATION OF ANY UNDERGROUND FIBER OPTIC CABLE AND APPURTENANCES SHALL BE PERFORMED BY SPRINT CABLE (PHONE: 214-707-1271).
 - ANY AND ALL DEMOLITION AND / OR RELOCATION OF ANY UNDERGROUND NATURAL GAS SUPPLY PIPING AND APPURTENANCES SHALL BE PERFORMED BY NICOR GAS (PHONE: 630-844-2040).
 - INSTALL 8 FT. HIGH CHAIN LINK TEMPORARY CONSTRUCTION FENCE PER I.D.O.T. 664001-02 WITH GATES WHERE SHOWN. ALL GATES TO BE CHAIN-LINK WITH (2) 10 FT. WIDE X 8' HIGH PANELS (20 FT. WIDE OPENINGS) AND HEAVY DUTY HENGEZ. GATES SHALL BE FURNISHED WITH LOCKS AND CHAINS. (4) KEYS FOR GATE LOCKS SHALL BE FURNISHED TO THE VILLAGE OF WINFIELD FOR ACCESS BY PUBLIC WORKS, POLICE, FIRE AND OTHER EMERGENCY VEHICLES. ERECTION OF FENCE SHALL BE COMPLETED AS DIRECTED BY THE ENGINEER AND BE MAINTAINED THROUGHOUT THE COURSE OF THE PROJECT BY THE CONTRACTOR. ANY TEMPORARY MODIFICATIONS IN FENCE PLACEMENT DURING THE PROJECT SHALL BE COORDINATED BY THE CONTRACTOR WITH THE APPROVAL OF THE ENGINEER AND THE U.P.R.R. THE CONTRACTOR SHALL INSTALL THE FENCE IN SUCH A MANNER THAT IT WILL CAUSE MINIMAL DISRUPTION WITH EXISTING UTILITIES AND LANDSCAPING. ANY REQUIRED TREE TRIMMING, RELOCATION OF PERMANENT SIGNS OR OTHER SUCH OBSTACLES SHALL BE INCIDENTAL TO THE COST OF TEMPORARY FENCE INSTALLATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY SAFETY WARNING SIGNS RELATED TO THE FENCE AND WORK AREA.
 - SIGNS AND WHEEL STOPS TO BE REMOVED SHALL BE STORED AT THE VILLAGE PUBLIC WORKS FOR RE-USE.

LEGEND

	TEMPORARY CONSTRUCTION FENCE (SEE NOTE 6)
	EXISTING PAVEMENT TO BE REMOVED
	SOIL BORING LOCATION PER THE GEOTECHNICAL INVESTIGATION PREPARED BY PATRICK ENGINEERING, INC. LITTLE, IL PROJ. NO. 20603.040, DATED JULY 2006
	EXISTING TREE TO BE REMOVED
	CURB TO BE REMOVED SAWCUT ALL EDGES
	PAVEMENT SAWCUT LINE
	EXISTING STORM SEWER TO BE REMOVED
	EXISTING FENCE TO BE REMOVED
	EXISTING UNDERGROUND ELECTRICAL CONDUIT TO BE REMOVED (SEE ELECTRICAL PLANS)

1/6/2009 4:11:12 PM N:\DOK\WF\WF451\SHEETS\WF451-C3-DEMO.DGN

This drawing shall not be used nor reproduced either wholly or in part except when authorized by the engineer- Rempe-Sharpe

ACTION	NAME	No.	Date	Revisions	By
Design	J.B.				
Drawn	D.B.E.				
Checked	E.J.				

REMPE-SHARPE CONSULTING ENGINEERS
 IL P.D.F. LICENSE NO. 184-000895
 324 WEST STATE STREET - GENEVA, ILLINOIS 60134
 Telephone (630) 232-0927 - Fax (630) 232-1629

PROJECT
PEDESTRIAN UNDERPASS AT METRA STATION WINFIELD, ILLINOIS

SHEET TITLE
EXISTING CONDITIONS, REMOVAL AND SITE PREPARATION PLAN

SCALE	PROJECT NO.	SHEET
1"=20'	WF-451	No. C3
	DATE	of C11
	DEC. 19, 2008	