



- NOTES:**
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DESIGN AND CONSTRUCT ALL TEMPORARY AND PERMANENT STEEL SHEET PILING TO COMPLY WITH AREMA 8.28.1.3. THE CONTRACTOR SHALL FURNISH CALCULATIONS AND DESIGN FILES PREPARED BY A LICENSED STRUCTURAL ENGINEER FOR APPROVAL PRIOR TO COMMENCING WITH SHEET PILING INSTALLATION.
  - ALL TEMPORARY SHEET PILING SHALL BE REMOVED AFTER ALL STRUCTURAL CONSTRUCTION IS IN PLACE (OR AS DIRECTED BY THE ENGINEER).
  - ALL PERMANENT SHEET PILING SHALL BE LOWERED BY CUTTING OFF AND DISPOSING SHEET PILING MATERIAL TO A MIN. OF 1.5 FT BELOW FINISHED GRADE (OR AS DIRECTED BY THE ENGINEER) AFTER ALL CONSTRUCTION IS IN PLACE AND PRIOR TO PLACEMENT OF PAVING MATERIALS OR TOPSOIL.

12/17/2008 1:48:43 PM IN:\DRN\WF\RES\SHSHEETS\WF451-C10-NRAMP-SECT.DGN

This drawing shall not be used or reproduced either wholly or in part except when authorized by the engineer- Rempe-Sharpe

ACTION	NAME	No.	Date	Revisions	By
Design	J.B.				
Drawn	D.B.E.				
Checked	E.J.				

**REMPE-SHARPE CONSULTING ENGINEERS**  
 IL P.D.F. LICENSE NO. 184-000895  
 324 WEST STATE STREET - GENEVA, ILLINOIS 60134  
 Telephone (630) 232-0827 - Fax (630) 232-1629

**PROJECT**  
 PEDESTRIAN UNDERPASS AT METRA STATION WINFIELD, ILLINOIS

**SHEET TITLE**  
 NORTH RAMP FULL SECTIONS

SCALE	PROJECT NO.	SHEET
NOTED	WF-451	No. <b>C10</b>
	DATE	Of <b>C11</b>
	DEC. 19, 2008	