

LOCAL RTE. M.S. 1040	SECTION 05-00010-00-PV	COUNTY HENRY	TOTAL SHEETS 136	SHEET NO. 8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION	PVC	56105300 WATER VALVES 16	60248900 V V TA 5 DIA TIF CL	XX006038 CONN EX W MN P 16
	FOOT	EACH	EACH	EACH
Lathrop Street				
STA. 5+65.07 RT				1
STA. 5+67.71, 115.50' RT TO 10+60.00, 30.00' RT	514.0			
STA. 5+67.71, 115.50' RT		1	1	
STA. 6+47.54, 30.0' RT				
TOTAL	514.0	1	1	1

EARTHWORK SUMMARY				
LOCATION	EARTH	EARTH EXC.	EMBANKMENT	EARTHWORK BALANCE
	EXCAVATION	ADJUSTED FOR SHRINKAGE		WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD	CUBIC YARD	CUBIC YARD
LATHROP STA. 5+24 TO STA. 24+50	3970	2978	1794	1184
LATHROP STA. 25+50 TO STA. 67+00	7664	5748	17649	-11901
LATHROP STA. 67+50 TO STA. 85+90	1208	906	10835	-9929
IL 78 STA. 106+75 TO STA. 109+50	68	51	0	51
2900E STA. 21+50 TO STA. 25+00	1007	755	3407	-2652
TOTAL	13917	10438	33685	-23247



SHIVE HATTERY
 Cedar Rapids, IA · Iowa City, IA · Des Moines, IA
 Moline, IL · Bloomington, IL · Chicago, IL

SHIVE-HATTERY, INC. 1701 RIVER DRIVE, SUITE 200 MOLINE, IL 61265
 PHONE (309) 764-7650 FAX (309) 764-8616
 http://www.shive-hattery.com
 ILLINOIS FIRM NUMBER: 184-000214

PLOT DATE * * * * *
 FILE NAME * * * * *
 PLOT SCALE * * * * *
 USER NAME * * * * *

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY MAC
 HORIZ. CHECKED BY PMH
 DATE 03-11-09

SCHEDULE OF QUANTITIES