SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY
20200410*	Earth Excavation (Special)	Cu. Yd.	295
20201200*	Removal and Disposal of Unsuitable Material	Cu. Yd.	150
20300100	Channel Excavation	Cu. Yd.	96
20700220	Porous Granular Embankment	Cu. Yd.	39
20800150*	Trench Backfill	Cu. Yd.	12
25000900*	Seeding, Class 1 (Special)	Acre	0.28
25100635	Heavy Duty Erosion Control Blanket	Sq. Yd.	603
28000400	Perimeter Erosion Barrier	Foot	535
28000500	Inlet and Pipe Protection	Each	4
28100109	Stone Riprap, Class A5	Sq. Yd.	57
28200200	Filter Fabric	Sq. Yd.	57
35100100	Aggregate Base Course, Type A	Ton	201
42000301*	Portland Cement Concrete Pavement 8" (Jointed)	Sq. Yd.	729
42001300	Protective Coat	Sq. Yd.	1,349
42300710*	Portland Cement Concrete Driveway Pavement, 6 inch, Special	Sq. Yd.	460
42400420*	Portland Cement Concrete Sidewalk 4 inch, Special	Sq. Ft.	487
50101500	Removal of Existing Superstructure	Each	1
50102400	Concrete Removal	Cu. Yd.	39.8
50200100	Structure Excavation	Cu. Yd.	59
50300225	Concrete Structures	Cu. Yd.	34.4
50300255	Concrete Superstructure	Cu. Yd.	107.5
50300260	Bridge Deck Grooving	Sq. Yd.	174
50300300	Protective Coat	Sq. Yd.	258
50800205	Reinforcement Bars, Epoxy Coated	Pound	27,570
Δ 50900905*	Removing and Re-Erecting Existing Railing	Foot	52
51500100	Name Plates	Each	1
550A0070*	Storm Sewers, Class A, Type 1 15"	Foot	34
550A0360*	Storm Sewers, Class A, Type 2 15"	Foot	130
550A0410*	Storm Sewers, Class A, Type 2 24"	Foot	24
55100700	Storm Sewer Removal 15"	Foot	127
55101200	Storm Sewer Removal 24"	Foot	25
60242600*	Inlets, Special, No. 2	Each	2
60500060	Removing Inlets	Each	2
60610100*	Combination Concrete Curb and Gutter, Type M-6.18 (Modified)	Foot	474
Δ 63100215*	Traffic Barrier Terminal, Type 6 (Special)	Each	1
63200310	Guardrail Removal	Foot	38
66410400*	Chain Link Fence to be Removed and Re-Erected	Foot	125
67100100	Mobilization	L. Sum	1
70101700*	Traffic Control and Protection	L. Sum	1
X0321556*	Sanitary Manholes to be Adjusted	Each	2
Z0005400*	Breaker-Run Crushed Stone	Ton	150

* Special Provisions
Δ Specialty Items

CONSTRUCTION TYPE CODE X081-2A

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | RT. OF WAY CHECKED | CADD FILE NAME | NOTE BOOK | NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | B.M. NOTED | STRUCTURE NOTATNS CHKD | NOTE BOOK | NO. | BY | DATE

FILE NAME = s:\Specs\ 1038R08 Independence Avenue\Drawings\ 1038_Summary of Quantities.dgn

WILLETT, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
809 East Second Street Dixon, IL 61021
Phone 815.284.3381 Fax 815.284.3385
Design Firm # 184-000918
www.willetthofmann.com

USER NAME =	DESIGNED - MAS	REVISED -	
	DRAWN - FDL	REVISED -	
PLOT SCALE =	CHECKED - BKC	REVISED -	
PLOT DATE =	DATE - 1-8-09	REVISED -	

CITY OF ROCKFORD
INDEPENDENCE AVENUE
OVER S. BRANCH OF KENT CREEK

Summary Of Quantities

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	98-00484-00-BR	WINNEBAGO	18	2
STA.	TO STA.	CONTRACT NO. 85453		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		