

SCHEDULES

PLAN	REPORTED	DATE
NO.	BY	
	DESIGNED	
	PLOTTED	
	ALIGNED	
	CHECKED	
	DATE	
	FILE NAME	

PROFILE	REPORTED	DATE
NO.	BY	
	DESIGNED	
	PLOTTED	
	ALIGNED	
	CHECKED	
	DATE	
	FILE NAME	

GUARD RAIL REMOVAL		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
RT. 19+37 TO 19+74	38	
PROJECT TOTAL	38	

CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED		
STATION	FOOT	REMARKS
INDEPENDENCE AVE.		
LT. 18+55 TO 19+71	125	
PROJECT TOTAL	125	

TRAFFIC CONTROL AND PROTECTION		
STATION	L SUM	REMARKS
INDEPENDENCE AVE.		
ENTIRE PROJECT	1	
PROJECT TOTAL	1	

SANITARY MANHOLES TO BE ADJUSTED		
STATION	EACH	REMARKS
INDEPENDENCE AVE.		
2' RT. 19+51	1	
1' LT. 20+56	1	
PROJECT TOTAL	2	

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
INDEPENDENCE AVE.		
CONTINGENCY ITEM	150	AS DIRECTED BY ENGINEER
PROJECT TOTAL	150	

FILE NAME = s:\rock\proj\103PR00-Independence\SSchedule.dgn

WILLET, HOFMANN & ASSOCIATES, INC.
CONSULTING ENGINEERS
 809 East Second Street Dixon, IL 61021
 Phone 815.294.3381 Fax 815.294.3385
 Design Firm # 194-00918
 www.willett-hofmann.com

USER NAME =	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE =	DATE -	REVISED -

CITY OF ROCKFORD
INDEPENDENCE AVENUE
OVER S. BRANCH OF KENT CREEK

Schedules

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	98-00484-00-BR	WINNEBAGO	18	4
STA.	TO STA.	CONTRACT NO. 85453		
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				