

**SUMMARY OF QUANTITIES**

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
					1000-2A	Y031-1F						1000-2A	Y031-1F
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	90	90			40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	564	564	
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	22	22			40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3651	3651	
	20200100	EARTH EXCAVATION	CU YD	26506	26506			40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	56	56	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500	500			42001300	PROTECTIVE COAT	SQ YD	7465	7465	
	20700220	POROUS GRANULAR EMBANKMENT	CU YD	500	500			42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	1070	1070	
	20800150	TRENCH BACKFILL	CU YD	2967	2967			42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8"	SQ YD	3304	3304	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	34541	34541			42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	51077	51077	
	21301052	EXPLORATION TRENCH, 52" DEPTH	FOOT	1700	1700			42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6"	SQ FT	2338	2338	
	25000110	SEEDING, CLASS 1A	ACRE	4	4			42400800	DETECTABLE WARNINGS	SQ FT	528	528	
	25000210	SEEDING, CLASS 2A	ACRE	4	4			44000100	PAVEMENT REMOVAL	SQ YD	19827	19827	
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	641	641			44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2182	2182	
	25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	641	641			44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	974	974	
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	641	641			44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4616	4616	
	25100120	MULCH, METHOD 2	TON	8	8			44000300	CURB REMOVAL	FOOT	1639	1639	
	25100630	EROSION CONTROL BLANKET	SQ YD	15993	15993			44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4943	4943	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2836	2836			44000600	SIDEWALK REMOVAL	SQ FT	353	353	
	28000300	TEMPORARY DITCH CHECKS	EACH	48	48			44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	405	405	
	28000400	PERIMETER EROSION BARRIER	FOOT	3086	3086			44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	116	116	
	28000500	INLET AND PIPE PROTECTION	EACH	43	43			44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	330	330	
	28100107	STONE RIPRAP, CLASS A4	SQ YD	105	105			48101200	AGGREGATE SHOULDERS, TYPE B	TON	42	42	
	28200200	FILTER FABRIC	SQ YD	105	105			SP	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
	31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ YD	4400	4400			SP	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
	31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	30764	30764				50105220	PIPE CULVERT REMOVAL	FOOT	1333	1333
	31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1683	1683			SP	50901720	BICYCLE RAILING	FOOT	269	269
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	182	182			SP	54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1
	35100700	AGGREGATE BASE COURSE, TYPE A, 8"	SQ YD	5191	5191			SP	54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1	1
SP	35401100	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, VARIABLE DEPTH	SQ YD	900	900				54010504	PRECAST CONCRETE BOX CULVERT, 5'x4'	FOOT	56	56
SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	2407	2407				54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	4	4
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	16498	16498				54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	EACH	1	1
	40600300	AGGREGATE (PRIME COAT)	TON	81	81				54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	EACH	1	1
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2				54216950	REINFORCED CONCRETE PIPE TEE, 30" PIPE WITH 18" RISER	EACH	2	2
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	187	187				54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	10	10
	40600990	TEMPORARY RAMP	SQ YD	230	230			SI	56109210	WATER VALVES TO BE ADJUSTED	EACH	21	21
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	19527	19527			SI	56400100	FIRE HYDRANTS TO BE MOVED	EACH	1	1

SI = SPECIALTY ITEM / SP = SPECIAL PROVISION