RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 20	06-00275-00-PV	LaSALLE	218	19
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 87352

STORM SEWER

STATION	OFFSET (FT.)	TYPE	STANDARD	STORM SEWER															INLETS						MANHOLES													
				CLASS A, TYPE 1									CLASS A, TYPE 2							TYPE A			TYPE B		4' DIAMETER			5' DIAMETER			6' DIAMETER		9' DIA.	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	TRENCH BACKFILL
				8"	10"	12"	15"	18"	24"	36"	42"	48"	12"	15"	18"	24"	30"	36"	48"	TYPE 3 F & G	TYPE 8 GRATE	TYPE 11 F & G	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 1 FRAME CLID, RES. PLATE	TYPE 1 FRAME CLID					
				FOOT															EACH																			CU YD
C.H. 20 (ETNA RD.)																																						
7+56.00	41.00 RT	INLET	602301, 604006																1																			
		SS		14																																		1
7+71.00	41.00 RT	INLET	602301, 604006																1																			
		SS			32																																	
8+50.00	42.92 RT	INLET	602301, 604006																1																			
		SS				22																																
8+44.20	63.69 RT	END SECTION	542301																																	1		
8+76.08	58.25 LT	EX. SS																																				
		SS				26																																
8+85.59	82.29 LT	END SECTION	542301																																	1		
9+85.82	78.67 LT	INLET	602301, 604006																1																			
		SS				4																																
9+92.05	80.00 LT	INLET BOX	542546																																1			
10+25.00	46.21 LT	INLET	602301, 604006																1																			
		SS											30																									6
10+01.56	45.11 RT	EX. INLET																																				
		SS													24																							10
10+09.21	71.10 RT	MANHOLE	602401, 604036, 602601																								1											
9+99.25	76.50 RT	MANHOLE	602401, 602601, 604001																						1													
		SS														10																						
10+09.21	71.10 RT	MANHOLE	602401, 604001, 602601																																			
		SS												44																								
10+50.00	49.00 RT	MANHOLE	602401, 604001, 602601																								1											
		SS											42																									21
10+90.00	29.00 RT	MANHOLE	602401, 604006, 602601																							1												
11+20.00	43.00 LT	INLET	602301, 604006																1																			
		SS											14																									2
11+05.00	43.00 LT	INLET	602306, 604006, 602601																				1															
		SS											14																									4
10+90.00	43.00 LT	INLET	602306, 604006, 602601																				1															
		SS											70																									43
		SS											12																									3
11+05.00	29.00 RT	INLET	602306, 602601, 604006																				1															
		SS											14																									2
11+20.00	29.00 RT	INLET	602301, 604006																1																			
		SS												148																								
12+00.00	1.00 RT	INLET	602301, 604051																			1																
		SS				44																																10
12+00.00	47.00 RT	MANHOLE	602401, 604001, 602601																								1											
		SS												48																								
12+50.00	47.00 RT	MANHOLE	602401, 604001, 602601																								1											
13+75.00	41.00 LT	INLET	602301, 604036																	1																		
		SS				98																																8
12+60.00	38.65 LT	INLET	602306, 604006, 602601																				1															
		SS											66																									18
12+60.00	28.93 RT	INLET	602306, 604006, 602601																				1															
		SS											18																									7
		SS											168																									54
13+95.00	58.00 RT	MANHOLE	602401, 604001, 602601																								1											
		SS				20																																3
14+00.00	37.55 RT	INLET	602301, 604006																1																			
		SS											228																									
16+25.00	40.26 RT	MANHOLE	602401, 604001, 602601																								1											
15+90.00	22.00 LT	INLET	602301, 604006																1																			
		SS											14																									2
16+05.00	22.00 LT	INLET	602306, 604006, 602601																				1															
		SS											48																									8
16+25.00	22.00 RT	INLET	602306, 604006, 602601																				1															
		SS											16																									2
16+95.00	22.00 LT	INLET	602301, 604006																1																			
		SS				44																																6
17+13.00	22.00 RT	INLET	602306, 604006, 602601																				1															
		SS				14																																2
17+15.00	37.86 RT	MANHOLE	602401, 604001, 602601																								1											
		SS											76																									
18+05.00	34.00 RT	MANHOLE	602401, 604001, 602601																						1													
18+00.00	22.00 LT	INLET	602301, 604006																1																			
		SS				44																																6
18+05.00	22.00 RT	INLET	602306, 604006, 602601																				1															
		SS											10																									3
		SS											68																									

STORM SEWER SCHEDULE CONTINUED ON NEXT SHEET