RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 20	06-00275-00-PV	LaSALLE	218	22
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 87352

STORM SEWER

STATION	OFFSET (FT.)	TYPE	STANDARD	STORM SEWER CLASS A, TYPE 1 8" (FOOT)	10"	12"	15"	18"	24"	36"	42"	48"	CLASS A, TYPE 2 12" (FOOT)	15"	18"	24"	30"	36"	48"	INLETS TYPE A TYPE 3 F & G	TYPE 8 GRATE	TYPE 11 F & G	TYPE B TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	MANHOLES 4' DIAMETER TYPE 1 FRAME CLID (EACH)	4' DIAMETER TYPE 3 F & G	4' DIAMETER TYPE 8 GRATE	5' DIAMETER TYPE 1 FRAME CLID	5' DIAMETER TYPE 3 F & G	5' DIAMETER TYPE 8 GRATE	6' DIAMETER TYPE 1 FRAME CLID	6' DIAMETER TYPE 1 FRAME CLID, RES. PLATE	9' DIA. TYPE 1 FRAME CLID	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	TRENCH BACKFILL (CU YD)
39+00.00	35.60 LT	INLET	602301, 604036																		1																	
		SS				46																																4
38+55.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS				44																																3
38+50.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS				10																																2
		SS												98																								6
39+50.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
39+86.61	24.93 LT	INLET	602301, 604006																	1																		
		SS											6																									2
39+83.67	31.99 LT	INLET	602306, 604006, 602601																					1														
		SS											14																									4
39+68.80	31.97 LT	INLET	602306, 604006, 602601																					1														
		SS											6																									1
39+65.87	24.92 LT	INLET	602306, 604006, 602601																					1														
		SS					14																															4
39+50.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS												56																								14
41+25.00	23.65 LT	INLET	602301, 604006																	1																		
		SS				10																																1
41+35.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS											64																									10
42+00.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS											58																									10
42+60.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS											44																									11
42+60.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS												10																								5
42+60.00	34.00 RT	INLET	602306, 604006, 602601																				1															
		SS												162																								25
44+25.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
44+25.00	22.00 RT	INLET	602306, 604006																					1														
		SS													10																							6
		SS													248																							
46+75.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
46+33.00	28.58 LT	INLET	602301, 604036																		1																	
		SS				44																																12
46+78.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS												44																								8
46+78.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS													10																							3
		SS													248																							20
49+25.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
49+15.00	28.58 LT	INLET	602301, 604036																		1																	
		SS				10																																
49+25.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS											44																									8
49+25.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS											10																									3
		SS													248																							41
51+75.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
51+65.00	28.58 LT	INLET	602301, 604036																		1																	
		SS											10																									
51+75.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS												44																								5
51+75.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS													10																							5
		SS													122																							
53+00.00	34.00 RT	MANHOLE	602401, 604001, 602601																							1												
52+90.00	28.58 LT	INLET	602301, 604036																		1																	
		SS				10																																
53+00.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS												44																								7
53+00.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS												10																								3
		SS													56																							6
53+58.24	41.77 RT	MANHOLE	602401, 604001, 602601																							1												
54+90.00	28.58 LT	INLET	602301, 604036																		1																	
		SS											10																									
55+00.00	22.00 LT	INLET	602306, 604006, 602601																					1														
		SS												44																								9
55+00.00	22.00 RT	INLET	602306, 604006, 602601																					1														
		SS												10																								5
55+10.00	28.00 RT	INLET	602306, 604001, 602601																				1															
		SS												172																								114

STORM SEWER SCHEDULE CONTINUED ON NEXT SHEET