RTE. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CH 20	06-00275-00-PV	LaSALLE	218	25
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 3	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 87352

STORM SEWER

STATION	OFFSET (FT.)	TYPE	STANDARD	STORM SEWER																INLETS						MANHOLES									FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 18"	TRENCH BACKFILL
				CLASS A, TYPE 1									CLASS A, TYPE 2							TYPE A			TYPE B			4' DIAMETER			5' DIAMETER			6' DIAMETER		9' DIA.					
				8"	10"	12"	15"	18"	24"	36"	42"	48"	12"	15"	18"	24"	30"	36"	48"	TYPE 3 F & G	TYPE 8 GRATE	TYPE 11 F & G	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 3 F & G	TYPE 8 GRATE	TYPE 1 FRAME CLID	TYPE 1 FRAME CLID, RES. PLATE	TYPE 1 FRAME CLID					
				FOOT																EACH																			CU YD
178+30.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											10																										4
		SS										58																											
178+90.00	27.57 LT	MANHOLE	602406, 604001, 602601																													1							
179+00.00	28.00 RT	INLET BOX	542546																															1					
		SS												14																									
178+90.00	15.00 RT	INLET	602306, 604006, 602601																					1															
		SS												30																									7
178+90.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS												10																									5
		SS										158																											
180+50.00	27.57 LT	MANHOLE	602401, 604001, 602601																													1							
180+50.00	15.00 RT	INLET	602301, 604006																	1																			
		SS											30																										5
180+50.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											10																										4
180+50.00	27.57 LT.	MANHOLE	602406, 604001, 602601																													1							
		SS									160																												
182+14.96	27.57 LT	MANHOLE	602401, 604001																														1						
183+85.00	30.00 RT	INLET	602301, 604001																		1																		
		SS				88																																	2
183+00.00	35.00 RT	INLET	602301, 604036, 602601																						1														
		SS											78																										8
182+25.00	15.00 RT	INLET	602301, 604036, 602601																					1															
		SS											30																										7
182+25.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											14																										7
		SS							104																														13
183+27.17	27.57 LT	MANHOLE	602406, 604001																														1						
		SS								20																													
183+50.00	27.57 LT	MANHOLE	602401, 604001, 602601																										1										
183+50.00	15.00 LT	INLET	602301, 604006																	1																			
		SS											10																										3
		SS																166																					
185+25.00	33.26 LT	MANHOLE	602401, 604001, 602601																											1									
185+25.00	15.00 RT	INLET	602301, 604006																	1																			
		SS				30																																	4
185+25.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											16																										4
		SS																90																					
186+18.00	27.57 LT	MANHOLE	602401, 604001, 602601																										1										
186+18.00	33.00 RT	INLET	602301, 604036																		1																		
		SS											16																										
186+18.00	15.00 RT	INLET	602306, 604001, 602601																					1															
		SS											40																										23
		SS																154																					
187+75.00	27.57 LT	MANHOLE	602401, 604006, 602601																										1										
187+50.00	34.00 RT	INLET	602301, 604036																		1																		
		SS											30																										
187+75.00	15.00 RT	MANHOLE	602401, 604006, 602601																								1												
188+50.00	33.00 RT	INLET	602301, 604036																		1																		
		SS											76																										28
		SS											30																										16
187+75.00	15.00 LT	INLET	602306, 604006, 602601																					1															
		SS											10																										7
187+75.00	43.00 LT	INLET	602301, 604036																		1																		
		SS											14																										
189+03+/-	50.00 LT	END SECTION	542301																																			1	
		SS																218																					253
189+95.00	21.00 LT	MANHOLE	602401, 604001, 602601																										1										
190+00.00	40.00 LT	INLET	602301, 604036																		1																		
		SS											18																										
190+05.00	30.00 RT	INLET	602301, 604036																		1																		
		SS											14																										
190+05.00	15.00 RT	INLET	602306, 604001, 602601																					1															
		SS											32																										9
190+00.00	15.00 LT	INLET	602306, 604001, 602601																					1															
		SS											6																										2

STORM SEWER SCHEDULE CONTINUED ON NEXT SHEET