

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	80% FED 20% STATE F.A.P. 781 (IL. RTE. 33)	
				4+920.234 TO 15+545.000	15+545.000 TO 16+016.000
				CONSTRUCTION CODE TYPE	
				I000-2A RURAL	I000-2A URBAN
54001015	BOX CULVERT END SECTION, CULVERT NO. 15	EACH	2	2	0
54001016	BOX CULVERT END SECTION, CULVERT NO. 16	EACH	2	2	0
54001017	BOX CULVERT END SECTION, CULVERT NO. 17	EACH	2	2	0
54001018	BOX CULVERT END SECTION, CULVERT NO. 18	EACH	2	2	0
54001019	BOX CULVERT END SECTION, CULVERT NO. 19	EACH	2	2	0
54001020	BOX CULVERT END SECTION, CULVERT NO. 20	EACH	2	2	0
54001021	BOX CULVERT END SECTION, CULVERT NO. 21	EACH	2	2	0
54001022	BOX CULVERT END SECTION, CULVERT NO. 22	EACH	2	0	2
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2	2	0
60500060	REMOVING INLETS	EACH	1	1	0
Δ * 63100045	TRAFFIC BARRIER TERMINAL TYPE 2	EACH	1	1	0
Δ * 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	10	10	0
Δ * 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	1	1	0
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	109	96	13
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	39	39	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	11	1
67100100	MOBILIZATION	L SUM	1	1	0
* 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0
* 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	0
* 70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	0
* 70101000	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331 (SPECIAL)	EACH	1	1	0
* 70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	5	4	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	20	5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	5	4	1
70106700	TEMPORARY RUMBLE STRIP	EACH	30	24	6
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	449	429	20
Δ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	24	24	0
Δ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12	0
MX033776	PRECAST CONCRETE BOX CULVERT 900MM x 450MM (M273)	METER	29.7	29.7	0.0

Δ Specialty Items
* SEE SPECIAL PROVISIONS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES SCALE _____ DRAWN BY KOJ DATE DECEMBER 22, 2008 CHECKED BY LWJ
NAME	DATE	

PLOT DATE = 1/29/2009
FILE NAME = H:\4420\Contract 94533\SH_004_sump_VB.dgn

H. M. & G. NO. 4420