

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	16
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**EARTHWORK SCHEDULE**

LOCATION		EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT REQUIRED	EMBANKMENT REQUIRED FOR ENTRANCES (SEE NOTE)	EARTH EXCAVATION AVAILABLE (ADJUSTED FOR SHRINKAGE - 25%)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION AND PLACEMENT
STATION		M2020010	M2020050	M2021200					M2112500
	RT/LT	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.
<b>RURAL</b>									
STA. 5+025 TO STA. 9+385	RT/LT	19226.4	1177.2		7737.8	6106.9	15302.7	1458.0	7666.1
STA. 5+194.097 (TR300)	RT.	127.8			44.0		95.9	51.9	19.0
STA. 6+444.9 (TR375)	LT.	68.8			72.5		51.6	-20.9	34.3
STA. 6+446 (TR375)	RT.	57.5			45.8		43.1	-2.7	37.5
STA. 7+687.148 (TR 450)	LT.	62.8			18.7		47.1	28.4	28.8
STA. 7+687.148 (TR 450)	RT.	56.0			21.6		42.0	20.4	33.9
STA. 8+910.897 (TR 525)	LT.	65.6			12.0		49.2	37.2	14.3
STA. 9+580 TO STA. 15+545	RT/LT	37501.7	1610.6	675.1	12074.9	13226.3	29334.2	4032.9	11454.2
STA. 10+125.278 (TR 600)	LT.	40.8			7.0		30.6	23.6	24.8
STA. 10+125.278 (TR 600)	RT.	69.9			60.8		52.4	-8.4	25.3
STA. 10+736.079 (FIREBAUGH)	RT.	53.7			16.8		40.3	23.5	21.1
STA. 12+164.026 (TR725)	LT.	103.9			31.0		77.9	46.9	15.6
STA. 12+164.026 (TR725)	RT.	123.8			14.0		92.9	78.9	8.0
STA. 13+391.693 (TR800)	LT.	66.4			17.0		49.8	32.8	17.7
STA. 13+391.693 (TR800)	RT.	155.2			3.0		116.4	113.4	30.8
STA. 15+062.4 (TR900)	LT.	103.1			23.0		77.3	54.3	19.3
STA. 15+062.4 (TR900)	RT.	63.6			3.0		47.7	44.7	25.0
	SUBTOT	57947.0	2787.8	675.1	20202.9	19333.2	45551.0	6014.9	19475.6
<b>URBAN</b>									
STA. 15+545 TO 16+016	RT/LT	2306.6	127.2		356.5	675.9	1825.4	792.9	720.9
STA. 15+661.3 (PASADENA)	RT.	50.3			10.0		37.7	27.7	11.3
STA. 15+773.3 (GLENDALE)	RT.	56.7			3.0		42.5	39.5	9.5
	SUBTOT	2413.6	127.2	0.0	369.5	675.9	1905.6	860.2	741.7
<b>TOTALS</b>		60360.6	2914.9	675.1	20572.4	20009.2	47456.6	6875.0	20217.3
<b>TOTALS ROUNDED FOR SUMMARY SHEET</b>		60365	2915	680					20220

NOTE: QUANTITIES ASSUME ALL EXISTING ENTRANCES (NOT INCLUDING PUBLIC ROADS) WILL BE REMOVED DURING DITCH EXCAVATION.

PLOT DATE = 12/22/2008  
 FILE NAME = H:\428\Contract\94533\SHT\_014\_sch\_all\_schedules\_18.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SCHEDULE OF QUANTITIES</b></p> <p>SCALE NO SCALE      DRAWN BY KOJ</p> <p>DATE DECEMBER 22, 2008      CHECKED BY LWJ</p>