

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**REMOVAL OF EXISTING STRUCTURES**

LOCATION		DESCRIPTION	REMOVAL OF EXISTING STRUCTURES
STATION	RT/LT		50100X00
<b>RURAL</b>			
STA 5+750	LT	1.8m X 7.3m STEEL PIPE BRIDGE AND FOUNDATION. THE BRIDGE CONSISTS OF 27 - 64mm DIAMETER STEEL PIPE	NO. 1
STA 7+446	LT	CONCRETE FOUNDATION TO BE REMOVED TO THE PROPOSED RIGHT-OF-WAY LINE. APPROX. 3.8m(L) X 3.4m(W)	NO. 2
STA 13+661	LT	CONCRETE WEIR; APPROX. 5.1 SQ. M	NO. 3
<b>URBAN</b>			
STA 15+654	RT	MASONRY COLUMN; APPROX. 600mm(L) X 600mm(W) X1200mm(H)	NO. 4
STA 15+666	RT	MASONRY COLUMN; APPROX. 600mm(L) X 600mm(W) X1200mm(H)	NO. 5

**REMOVING MANHOLES/INLETS**

LOCATION			REMOVING INLETS
STATION	DIST	RT/LT	60500060
<b>RURAL</b>			
STA 14+773.1	12.0 m	RT	1
<b>TOTAL</b>			<b>1</b>

**BUILDING REMOVAL**

LOCATION		BUILDING REMOVAL NO. 1
STATION	RT/LT	L. SUM
STA. 13+290	LT	1
<b>TOTAL</b>		<b>1</b>

PLOT DATE = 12/22/2008  
FILE NAME = H:\428\Contract\94533\SHT\_B\M\_sch\_all\_schedules\_V8.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
SCALE	DRAWN BY KOJ	CHECKED BY LWJ
DATE DECEMBER 22, 2008		