

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	1YRS	CRAWFORD	212	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**INLET AND PIPE PROTECTION**

STATION	SIDE	QUANTITY EACH	STATION	SIDE	QUANTITY EACH
5+096	RT	1	10+747	LT	1
5+153	LT	1	10+749	RT	1
5+203	LT&RT	2	10+773	LT	1
5+354	LT	1	10+801	LT	1
5+355	RT	1	10+833	LT	1
5+457	LT	1	10+889	RT	1
5+606	RT	1	10+922	LT	1
5+612	LT	1	10+927	RT	1
5+639	RT	1	11+137	LT	1
5+712	LT	1	11+256	RT	1
5+778	LT	1	11+315	LT	1
5+945	RT	1	11+584	RT	1
6+092	RT	1	11+741	LT	1
6+148	RT	1	11+894	RT	1
6+187	LT	1	11+926	RT	1
6+189	RT	1	12+345	RT	1
6+309	RT	1	12+346	LT	1
6+438	RT	1	13+000	LT	1
6+450	LT	1	13+068	LT	1
6+455	RT	1	13+095	RT	1
6+494	RT	1	13+105	LT	1
6+511	LT	1	13+147	LT	1
6+553	LT	1	13+172	LT	1
6+562	RT	1	13+214	LT	1
6+583	LT	1	13+255	LT	1
6+624	RT	1	13+339	LT	1
6+628	LT	1	13+472	LT	1
6+644	LT	1	13+482	RT	1
6+738	RT	1	13+518	RT	1
6+776	RT	1	13+595	RT	1
6+810	RT	1	13+680	RT	1
6+896	RT	1	13+762	RT	1
7+080	RT	1	13+812	LT	1
7+026	LT	1	13+813	RT	1
7+054	RT	1	13+992	LT	1
7+166	RT	1	14+088	RT	1
7+301	LT	1	14+224	RT	1
7+339	LT	1	14+230	LT	1
7+403	LT	1	14+241	RT	1
7+478	LT	1	14+252	LT	1
7+486	RT	1	14+434	RT	1
7+515	LT	1	14+439	LT	1
7+680	RT	1	14+544	LT	1
7+692	RT	1	14+592	LT	1
7+697	LT&RT	2	14+618	RT	1
7+762	LT	1	14+621	LT	1
8+050	RT	1	14+653	LT	1
8+170	RT	1	14+654	RT	1
8+303	LT	1	14+687	RT	1
8+320	RT	1	14+703	LT	1
8+463	LT&RT	2	14+718	RT	1
8+570	LT	1	14+751	LT	1
8+615	RT	1	14+754	RT	1
8+623	LT	1	14+797	LT	1
8+643	LT	1	14+873	RT	1
8+660	RT	1	14+896	RT	1
8+678	RT	1	14+935	LT&RT	2
8+717	RT	1	14+990	LT	1
8+731	LT	1	15+243	LT	1
8+741	RT	1	15+332	LT	1
8+761	LT	1	15+361	LT	1
8+770	RT	1	15+376	LT&RT	2
8+783	LT	1	15+460	RT	1
8+854	RT	1	15+465	LT	1
8+855	LT	1	15+519	RT	1
8+881	RT	1	15+520	LT	1
8+939	RT	1	15+535	LT&RT	2
9+065	LT	1	15+606	LT	1
9+181	RT	1	15+671	LT&RT	2
9+691	RT	1	15+733	RT	1
9+717	RT	1	15+863	RT	1
10+329	RT	1	15+864	LT	1
10+340	LT	1	15+884	LT	1
10+511	LT	1	15+924	RT	1
10+570	RT	1	15+951	LT	1
10+714	RT	1			
SUB-TOTAL		79	SUB-TOTAL		79
GRAND TOTAL			GRAND TOTAL		158

**BOX CULVERT SCHEDULE**

CULV. NO.	STATION	RT/LT/AR	TYPE	M273				PRECAST CONCRETE BOX CULVERT END SECTION EACH	TRAFFIC CONTROL AND PROTECTION STANDARD 701321 EACH
				3.0m x 0.9m	750 x 450	900 x 450	1.2m x 0.6m		
<b>RURAL</b>									
8	STA 5+750.192	AR	EXTENSION	See Structure Plans For Quantities					
9	STA 6+430.000	AR	BOX CULVERT			16.20		2	1
10	STA 7+189.092	AR	EXTENSION	See Structure Plans For Quantities					
11	STA 7+421.533	AR	EXTENSION	See Structure Plans For Quantities					
12	STA 7+687.147	LT	BOX CULVERT		18.30			2	
13	STA 7+687.147	RT	BOX CULVERT		18.30			2	
14	STA 8+080.000	AR	BOX CULVERT	21.60				2	1
15	STA 8+828.407	AR	EXTENSION	See Structure Plans For Quantities					
16	STA 11+203.000	AR	EXTENSION	See Structure Plans For Quantities					
17	STA 12+895.187	AR	EXTENSION	See Structure Plans For Quantities					
18	STA 13+375.000	AR	BOX CULVERT			16.20		2	
19	STA 13+660.000	AR	BOX CULVERT	21.60				2	
20	STA 15+172.500	AR	BOX CULVERT				14.40	2	1
21	STA 15+376.500	AR	BOX CULVERT			13.50		2	1
<b>URBAN</b>									
22	STA 15+940.000	AR	BOX CULVERT		14.40			2	1
TOTALS				43.20	51.00	29.70	30.60	18	5
TOTALS ROUNDED FOR SUMMARY SHEET				43.2	51.0	29.7	30.6	18	5

**PAVEMENT MARKING SCHEDULE**

LOCATION	SHORT TERM PAVEMENT MARKING	TEMPORARY PAINT PAVEMENT MARKING LINE		PAINT PAVEMENT MARKING LINE		RAISED REFLECTIVE PAVEMENT MARKER (EACH)
		100 MM		100 MM		
		WHITE	YELLOW	WHITE	YELLOW	
STATION TO STATION	METER	METER	METER	METER	METER	
<b>RURAL</b>						
4+920.234 TO 5+025.0	41.9	209.5	26.2	209.5	26.2	5
5+025.0 TO 9+385.0	1,744.0	8,503.6	3,771.0	8,503.6	3,771.0	179
9+580.0 TO 13+750.733	1,668.3	8,085.5	3,907.7	8,085.5	3,907.7	171
13+752.021 TO 15+545.0	717.2	3,527.4	448.2	3,527.4	448.2	74
SUBTOTAL		4,171.4	20,326.0	8,153.1	20,326.0	429
<b>URBAN</b>						
15+545.0 TO 16+016.0	188.4	856.9	117.8	856.9	117.8	20
TOTALS		4,359.8	21,182.9	8,270.9	21,182.9	449
TOTALS ROUNDED FOR SUMMARY SHEET		4,360	21,183	8,271	21,183	449

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
SCALE	NO SCALE	DRAWN BY KOJ
DATE	DECEMBER 22, 2008	CHECKED BY LWJ

PLOT DATE = 12/22/2008  
FILE NAME = H:\V\20\Contract 94533\SHIT\_014\_sch.ctb\all\_schedules\_V8.dgn

H. M. & G. NO. 4420