

PLANTING SCHEDULE

DESIGNATION	BOTANICAL NAME	COMMON NAME	QUANTITY PER SHEET							TOTAL	SIZE
			85	86	87	88	89	90			
SHADE TREES											
AF	ACER X 'FREEMANII'	FREEMAN MAPLE	0	5	3	5	6	0	19	3" BB	
GTS	GLEDITSIA TRIACANTHOS 'SKYLINE'	SKYLINE HONEYLOCUST	0	0	0	3	2	0	5	3" BB	
QR	QUERCUS RUBRA	RED OAK	0	0	0	0	1	0	1	3" BB	
TAL	TILIA AMERICANA 'LINCOLN'	LINCOLN AMERICAN LINDEN	0	0	0	0	0	0	0	3" BB	
UA	ULMUS 'ACCOLADE'	ACCOLADE ELM	0	0	2	5	0	0	7	3" BB	
SHRUBS											
AA	ARONIA ARBUTIFOLIA 'BRILLIANTISSIMA'	BRILLIANTISSIMA RED CHOKEBERRY	0	35	15	67	23	0	140	3-GAL. 36" HT.	
CKF	CALAMAGROSTIS 'KARL FOERSTER'	KARL FOERSTER REED GRASS	0	0	0	0	0	0	0	1-GAL. 36" HT.	
IG	ILEX GLABRA	INKBERRY	0	43	43	0	18	72	176	5-GAL. 36" HT.	
JSB	JUNIPERUS SABINA 'BUFFALO'	BUFFALO JUNIPER	12	0	0	0	0	0	12	3-GAL. 36" HT.	
LVL	LIGUSTRUM VULGARE 'LODENSE'	DWARF COMMON PRIVET	0	0	0	65	0	0	65	3-GAL. 36" HT.	
RKO	ROSA X 'KNOCK OUT'	KNOCK OUT ROSE	4	0	8	8	12	8	40	3-GAL. 36" HT.	
SBF	SPIRAEA X BUMALDA 'FROEBELII'	FROEBELII SPIREA	0	0	79	0	58	0	137	3-GAL. 36" HT.	
PERENNIAL MIX / SOD											
PM (SF)	PERENNIAL MIX		0	133	527	202	357	228	1,447	1 GAL., WELL DEVELOPED	
SAJ	SEDUM 'AUTUMN JOY'	AUTUMN JOY SEDUM	40	0	0	0	0	0	40	1-GAL. 18" HT.	
SOD (SY)			0	0	170	41	93	146	450		
LIRIOPE (SY)	LIRIOPE SPICATA	CREeping LILYTURF	0	69	70	141	112	0	392	4" POTS 12" SPACING (9/SY)	

TOPSOIL SCHEDULE

EASEMENT AREA	12" DEPTH SQ. YD. QUANTITY	24" DEPTH SQ. YD. QUANTITY	48" DEPTH SQ. YD. QUANTITY
A	N/A	N/A	N/A
B	N/A	N/A	N/A
C	N/A	N/A	N/A
D	45	25	0
E	N/A	N/A	N/A
F	N/A	N/A	N/A
G	70	46	16
H	0	16	4
I	0	29	0
J	N/A	N/A	N/A
K	61	47	20
L	181	86	0
M	31	10	0
N	62	80	20
O	64	36	12
P	9	6	0
Q	25	11	4
R	31	15	4
S	0	0	0
T	72	36	12
U	62	30	12
V	46	23	4
W	55	27	0
X	27	41	14
Y	33	14	0
TOTAL	921	621	134

FENCE SCHEDULE

EASEMENT AREA	QUANTITY LINEAR FEET
A	N/A
B	N/A
C	N/A
D	70'
E	N/A
F	N/A
G	100'
H	37'
I	50'
J	N/A
K	129'
L	0'
M	0'
N	70'
O	N/A
P	88'
Q	0'
R	32'
S	17'
T	49'
U	0'
V	0'
W	106'
X	89'
Y	63'
Z	71'
AA	95'
AB	0'
TOTAL	1094'

IRRIGATION SCHEDULE

EASEMENT AREA	ZONE VALVES (EACH)	QUICK COUPLER (EACH)	DRIP LINE (LINEAR FEET)
A	1	1	253'
B	1	0	100'
C	1	1	160'
D	1	2	606'
E	1	1	35'
F	1	1	103'
G	0	0	238'
H	0	0	47'
I	1	1	450'
J	1	1	100'
K	0	0	178'
L	0	0	66'
M	1	1	89'
N	1	1	87'
O	1	1	360'
P	1	2	576'
Q	1	1	83'
R	0	0	291'
S	1	1	567'
T	1	0	313'
U	1	0	20'
V	1	1	80'
W	1	1	111'
X	0	0	222'
Y	0	0	0'
Z	1	1	253'
AA	1	1	220'
AB	1	1	172'
AC	0	1	195'
AD	1	1	293'
AE	0	0	0'
TOTAL	22	22	6268'

Massie Massie & Associates
LAND PLANNING AND LANDSCAPE ARCHITECTURE
421 West Main Street, Decatur, IL 62522 217/424-0792
www.Massie-Massie-Associates.com

USER NAME =	DESIGNED — KLM	REVISED — 2/12/09
PLOT SCALE =	DRAWN — MRG	REVISED — 3/12/09
PLOT DATE =	CHECKED — KLM	REVISED —
	DATE — 1/15/09	REVISED —

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLANTING SCHEDULE

SCALE: N/A SHEET 94 OF 94 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	CITY	TOTAL SHEETS	SHEET NO.
323	06-00625-00-SW	DECATUR	121	94
ELDORADO STREETSCAPE PROJECT CONTRACT NO. 95574				
FED. ROAD DIST. NO. — ILLINOIS FED. AID PROJECT: TE-0007(35)				