FAU ROUTE	IDOT SECTION	COUNTY
9277	04-00031-00-PV	ST. CLAIR
FEDERAL AID PROJECT		ILLINOIS
IDOT JOB NO. C-98-309-06		
IDOT CONTRACT NO. 97327		

PAVEMENT MARKING SCHEDULE

LOCATION (STATION, DIRECTION)				TYPE	THERMOPLASTIC PAVEMENT MARKING – LETTERS & SYMBOLS (SQ FT) 78000100	THERMOPLASTIC PAVEMENT MARKING – LINE 4" (FOOT) 78000200	THERMOPLASTIC PAVEMENT MARKING – LINE 8" (FOOT) 78000500	THERMOPLASTIC PAVEMENT MARKING – LINE 12" (FOOT) 78000600	THERMOPLASTIC PAVEMENT MARKING – LINE 24" (FOOT) 78000650	PAINT PAVEMENT MARKING– LETTERS & SYMBOLS (SQFT) 78001100	PAINT PAVEMENT MARKING – LINE 4" (FOOT) 78001110	TEMPORARY PAVEMENT MARKING, LETTERS & SYMBOLS (SQ FT) 70300210	TEMPORARY PAVEMENT MARKING – LINE 4" (FOOT) 70300220	TEMPORARY PAVEMENT MARKING – LINE 8" (FOOT) 70300250	TEMPORARY PAVEMENT MARKING – LINE 12" (FOOT) 70300260	TEMPORARY PAVEMENT MARKING – LINE 24" (FOOT) 70300280	PAVEMENT MARKINGS REMOVAL (SQ FT) 78300100	RAISED REFLECTIVE PAVEMENT MARKERS (EACH) 78100100	REMOVE SIGN PANEL –TYPE 1 (SQ FT) 72400310	RELOCATE SIGN PANEL –TYPE 1 (SQ FT) 72400710	SIGN PANEL – TYPE 1 (SQ FT) 72000100	TELESCOPING STEEL SIGN SUPPORT (FOOT) 72800100
HUNTWOOD ROAD																						
26+95.55	CL	28+30.00	CL	DOUBLE YELLOW		268.9							268.9									
27+55.00	RT	28+30.00	RT	SOLID WHITE (TURN LANE)		75.0							75.0									
28+00.00				LT TURN ARROW	15.6							15.6										
28+30.00				WHITE STOP BAR				32.0							32.0							
28+34.00				CROSS WALK			65.0							65.0								
28+40.00				CROSS WALK			80.0							80.0								
29+10.00	CL	30+45.00	CL	DOUBLE YELLOW		270.0							270.0									
29+10.00	LT	29+85.00	LT	SOLID WHITE (TURN LANE)		75.0							75.0									
29+10.00				WHITE STOP BAR				27.0							27.0							
29+10.00	RT	30+45.00	RT	TWO-WAY AMBER														4				
29+10.00	LT	29+85.00	LT	ONE-WAY CRYSTAL														3				
29+40.00				LT TURN ARROW	15.6							15.6										
30+20.51	RT			SCHOOL	32.3							32.3										
31+38.00				BI-DIR ARROWS	31.2							31.2										
30+45.00	RT	37+45.00	RT	SOLID YELLOW		700.0							700.0									
30+45.00	RT	37+45.00	RT	SKIP-DASH YELLOW		180.0							180.0									
30+45.00	LT	37+45.00	LT	SOLID YELLOW		700.0							700.0									
30+45.00	LT	37+45.00	LT	SKIP-DASH YELLOW		180.0							180.0									
30+45.00	RT/LT	37+45.00	RT/LT	TWO-WAY AMBER														34				
30+45.40	RT			(R3-9B) 24"x 36"																	6.0	15.0
33+38.00				BI-DIR ARROWS	31.2							31.2										
35+38.00				BI-DIR ARROWS	31.2							31.2										
37+38.00				BI-DIR ARROWS	31.2							31.2										
37+45.00	LT	38+80.00	LT	DOUBLE YELLOW		270.0							270.0									
37+45.00	LT	38+80.00	LT	TWO-WAY AMBER														4				
37+45.98	LT			(R3-9B) 24"x 36"																	6.0	15.0
38+05.00	RT	38+80.00	RT	SOLID WHITE (TURN LANE)		75.0							75.0									
38+05.00	RT	38+80.00	RT	ONE-WAY CRYSTAL														3				
38+24.00				LT TURN ARROW	15.6							15.6										
38+29.35	RT			SCHOOL XING SIGNS															7.4	7.4		
38+59.00				LT TURN ARROW	15.6							15.6										
38+80.00				WHITE STOP BAR				24.0							24.0							
39+45.00				CROSS WALK			52.0							52.0								
39+45.00				DIAGONAL CROSS WALK				90.0							90.0							
39+51.00				CROSS WALK			45.0							45.0								
39+55.00	RT	40+90.00	RT	DOUBLE YELLOW		270.0							270.0									
39+55.00	LT	40+30.00	LT	SOLID WHITE (TURN LANE)		75.0							75.0									
39+55.00				WHITE STOP BAR				24.0							24.0							
39+55.00	RT	40+90.00	RT	TWO-WAY AMBER														4				
39+55.00	LT	40+30.00	LT	ONE-WAY CRYSTAL														3				
39+67.00				LT TURN ARROW	15.6							15.6										
39+94.51	LT			SCHOOL XING SIGNS															8.9	8.9		
40+12.00				LT TURN ARROW	15.6							15.6										
40+90.00	LT	47+22.00	LT	SOLID YELLOW		632.0							632.0									
40+90.00	LT	47+22.00	LT	SKIP-DASH YELLOW		160.0							160.0									
40+90.00	RT	47+22.00	RT	SOLID YELLOW		632.0							632.0									
40+90.00	RT	47+22.00	RT	SKIP-DASH YELLOW		160.0							160.0									
40+90.00	RT/LT	47+22.00	RT/LT	TWO-WAY AMBER														30				
40+96.40	RT			(R3-9B) 24"x 36"																	6.0	15.0
41+15.00				BI-DIR ARROWS	31.2							31.2										
43+15.00				BI-DIR ARROWS	31.2							31.2										
45+15.00				BI-DIR ARROWS	31.2							31.2										
46+05.00	LT			SCHOOL	32.3							32.3										
47+15.00				BI-DIR ARROWS	31.2							31.2										
47+22.00	LT	48+57.00	LT	DOUBLE YELLOW		270.0							270.0									
47+22.00	LT	48+57.00	LT	TWO-WAY AMBER														4				
47+26.29	LT			(R3-9B) 24"x 36"																	6.0	15.0
47+82.00	RT	48+57.00	RT	SOLID WHITE (TURN LANE)		75.0							75.0									
47+82.00	RT	48+57.00	RT	ONE-WAY CRYSTAL														3				
48+00.00				LT TURN ARROW	15.6							15.6										
48+30.00				LT TURN ARROW	15.6							15.6										
48+57.00				WHITE STOP BAR				24.0							24.0							
48+61.00				CROSS WALK			40.0							40.0								
48+67.00				CROSS WALK			42.0							42.0								
49+20.00				CROSS WALK			40.0							40.0								
49+26.00				CROSS WALK			38.0							38.0								
49+27.68	RT	50+65.00	RT	SKIP-DASH YELLOW		270.0							270.0									
49+27.68	LT	50+05.00	LT	SOLID WHITE (TURN LANE)		75.0							75.0									
49+27.68				WHITE STOP BAR				24.0							24.0							
49+27.68	RT	50+65.00	RT	TWO-WAY AMBER														4				
49+27.68	LT	50+05.00	LT	ONE-WAY CRYSTAL														3				
49+45.00	RT			SCHOOL	32.3							32.3										
49+50.00				LT TURN ARROW	15.6							15.6										
49+85.00				LT TURN ARROW	15.6							15.6										
50+65.00	RT	65+55.00	RT	SOLID YELLOW		1,490.0							1,490.0									
50+65.00	RT	65+55.00	RT	SKIP-DASH YELLOW		370.0							370.0									
50+65.00	LT	65+55.00	LT	SOLID YELLOW		1,490.0							1,490.0									
50+65.00	LT	65+55.00	LT	SKIP-DASH YELLOW		370.0							370.0									
50+65.00	LT/RT	65+55.00	LT/RT	TWO-WAY AMBER														72				
51+00.00	RT			(R3-9B) 24"x 36"																	6.0	15.0
51+60.00				BI-DIR ARROWS	31.2							31.2										
53+60.00				BI-DIR ARROWS	31.2							31.2										
54+63.72	RT			XING	20.3							20.3										
54+62.79	RT			SCHOOL XING SIGNS															7.0	7.0		
54+87.00				CROSS WALK			38.0							38.0								
54+87.00				DIAGONAL CROSS WALK				94.0							94.0							
54+93.00				CROSS WALK			41.0							41.0								
55+16.81				SCHOOL XING SIGNS															7.0	7.0		
55+16.17	LT			XING	20.3							20.3										
55+60.00				BI-DIR ARROWS	31.2							31.2										
55+64.83	LT	56+73.35	LT	ELEM. SCH.PK. LOT						15.6	650.0		650.0		540.0		275.9					
57+35.00				BI-DIR ARROWS	31.2							31.2										
58+00.00	LT			(R3-9B) 24"x 36"																	6.0	15.0
58+00.00	RT			(R3-9B) 24"x 36"																	6.0	15.0
59+35.00				BI-DIR ARROWS	31.2							31.2										

(PAVEMENT MARKING SCHEDULE CONITINUED ON NEXT SHEET)

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS ◆ SURVEYORS ◆ PLANNERS
TWM
☒ CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (318) 624-4488
FAX (618) 624-6688
corp@twm-inc.com
☐ EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com
☐ ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-5052
FAX (314) 872-2194
stlouis@twm-inc.com
☐ WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

SEAL

Signature:
Signature Date:
Expiration Date:

STATEMENT OF RESPONSIBILITY
I hereby confirm that the document herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

TITLE: SCHEDULE OF QUANTITIES

PROJECT: HUNTWOOD ROAD RECONSTRUCTION
VILLAGE OF SWANSEA
ST. CLAIR COUNTY

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY:	BJC	SHEET 11 OF 104 SHEETS	
DESIGNED BY:	BJG		
CHECKED BY:	SJK		
APPROVED BY:	SJK	PROJECT DESCRIPTION: Huntwood Road ReConstruction	
PROJECT NUMBER:	T20-030356		

☒ ISSUED FOR REVIEW ☐ ISSUED FOR BIDDING
☐ ISSUED FOR CONSTR. ☐ RECORD DRAWING

P:\030356\dwg\Roadway Plans\ROADWAY PLANS\030356 SCH1.dwg 5/23/2008 7:40:07 AM CDT