FAU ROUTE	IDOT SECTION	COUNTY
9277	04-00031-00-PV	ST. CLAIR
FEDERAL AID PROJECT		ILLINOIS
IDOT JOB NO. C-98-309-06		
IDOT CONTRACT NO. 97327		

PAVING AND SIDEWALK SCHEDULE

LOCATION (STATION TO STATION)				PROCESSING MODIFIED SOILS (SQ YD) 30200650	LIME (TON) 30201500	HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N 70 (TON) 40603085	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N 70 (TON) 40603340	AGGREGATE BASE COURSE, TYPE B - 8" (SQ YD) 35102000	FILTER FABRIC (SQ YD) 28200200	BIT. MATLS. (PRIME COAT) (TON) 40300200	BIT. MATLS. (CVR. & SEAL COAT) (TON) 40300400	COVER COAT AGGREGATE (TON) 40300500	SEAL COAT AGGREGATE (TON) 40300600	PORTLAND CEMENT CONCRETE SIDEWALK - 4" (SQ FT) 42400100	DETECTABLE WARNINGS (SQ FT) 42400800	CLASS SI CONCRETE (OUTLET) (CU YD) 60600095	CONCRETE CURB, TYPE B (FOOT) 60600605	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 (FOOT) 60605000
HUNTWOOD ROAD																		
27+67.67		29+57.85		2,094.0	40.3	935.5	220.1											
27+67.67	LT	14+74.36 OLD CASEYVILLE RD	LT											870.8	12.0			
27+67.67	LT	14+24.41 OLD CASEYVILLE RD	LT															151.8
27+67.67	RT	12+00.88 OLD CASEYVILLE RD	LT															154.8
28+05.44	RT	12+54.00 OLD CASEYVILLE RD	LT											257.0	12.0			
12+00.88 OLD CASEYVILLE RD	RT	29+57.85	RT															153.0
14+24.41 OLD CASEYVILLE RD	RT	29+57.85	LT															136.9
29+02.00	LT	30+46.00	LT											692.0	12.0			
29+57.85		66+54.57		17,317.8	333.5	7,038.6	1,656.1											
29+57.85	RT	35+22.00	RT															564.2
29+57.85	LT	38+80.98	LT															923.1
30+73.00	LT	31+60.00	LT															100.0
30+76.00	LT	38+95.00	LT											3,753.0	12.0			
35+22.00	RT	WEST RADIUS																52.0
35+95.00	RT	EAST RADIUS																48.0
35+95.00	RT	38+76.00	RT															281.0
38+76.00	RT	WEST RADIUS																42.0
38+80.98	LT	39+07.01	LT															41.0
39+32.01	LT	39+54.90	LT															41.0
39+45.00	LT	48+65.00	LT											2,775.5	24.0			
39+45.00	RT	51+35.00	RT											5,155.0	72.0			
39+54.90	LT	48+58.17	LT															903.3
39+65.00	RT	EAST RADIUS																42.0
39+65.00	RT	51+24.00	RT															1,159.0
40+67.24	LT	40+69.68	LT														11.5	
40+95.84	LT	41+04.13	LT														19.0	
43+41.55	LT	43+49.84	LT														16.5	
43+69.84	LT	43+78.13	LT														16.7	
45+22.93	RT	45+38.23	RT														31.3	
45+54.75	RT	45+61.81	RT														22.7	
47+12.32	RT	47+20.60	RT														17.4	
47+46.56	RT	47+54.99	RT														18.8	
48+58.17	LT	48+80.49	LT															40.0
48+68.48	RT	48+71.76	RT														28.7	
49+05.76	RT	49+09.07	RT														21.6	
49+05.43	LT	49+27.74	LT															40.0
49+18.00	LT	55+50.00	LT											2,672.5	60.0			
49+27.74	LT	66+54.37	LT															1,726.6
50+48.51	LT	50+53.10	LT														13.1	
50+90.08	LT	50+98.40	LT														16.9	
51+24.25	RT	51+46.57	RT															36.0
51+25.09	LT	51+29.69	LT														11.2	
51+53.69	LT	51+58.29	LT														11.7	
51+71.40	RT	52+00.00	RT															36.0
51+83.00	RT	58+66.96	RT											3,084.0	48.0			
51+90.74	LT	51+95.40	LT														12.5	
52+00.00	RT	55+10.00	RT															310.0
52+19.34	LT	52+23.94	LT														13.1	
52+58.65	LT	52+76.36	LT														41.1	
52+95.25	LT	53+28.25	LT														54.2	
55+10.00	RT	WEST RADIUS																55.0
55+26.88	LT	55+51.25	LT														46.2	
55+80.00	LT	66+54.37	LT											5,123.0	36.0			
55+86.60	LT	55+87.79	LT														26.5	
56+28.00	RT	EAST RADIUS																60.0
56+28.00	RT	60+20.00	RT															392.0
56+46.08	LT	56+51.49	LT														33.3	
56+85.35	LT	57+10.31	LT														39.1	
60+20.41	RT	60+32.02	RT															18.0
60+53.93	RT	60+63.54	RT															18.0
60+63.00	RT	65+13.00	RT															450.0
65+12.56	RT	65+22.27	RT															40.4
65+47.01	RT	65+56.62	RT															40.4
65+56.62	RT	67+09.23	RT															153.2
66+54.37	LT	194+74.94	LT											657.0	12.0			
66+54.37	LT	194+74.94 IL RTE 159	LT															125.0
66+54.57		67+60.00		785.4	15.1	323.1	76.0											
67+09.23	RT	192+72.91 IL RTE 159	LT															132.0
67+21.00	RT	192+72.91 IL RTE 159	LT											435.0	12.0			
194+39.00	RT	194+50.00 IL RTE 159	RT											78.0	24.0			
194+74.11	RT	194+97.00	RT											114.5				
SUB-TOTAL				20,197.2	389.0	8,297.1	1,952.2	0.0		0.0	0.0	0.0	0.0	25,667.30	336.0	0.0	523.1	8,465.6
DETOUR ROAD																		
37+50.00	RT	38+81.00	RT					76.2	76.2	0.1	0.2	0.8	0.8					
39+52.00	RT	45+27.00	RT					532.2	532.2	0.8	1.6	5.3	5.3					
45+54.00	RT	47+21.00	RT					165.3	165.3	0.3	0.5	1.7	1.7					
47+48.00	RT	48+72.00	RT					141.3	141.3	0.2	0.4	1.4	1.4					
49+04.00	RT	49+87.00	RT					109.6	109.6	0.2	0.3	1.1	1.1					
50+70.00	RT	51+38.00	RT					93.3	93.3	0.2	0.3	0.9	0.9					
51+66.00	RT	55+00.00	RT					386.1	386.1	0.6	1.1	3.9	3.9					
SUB-TOTAL				0.0	0.0	0.0	0.0	1,503.9	1,503.9	2.4	4.4	15.0	15.0	0.0	0.0	0.0		0.0
OLD CASEYVILLE ROAD																		
11+67.29	RT	12+00.88	RT													2.5		
11+71.81	LT	12+00.88	LT													2.3		
SUB-TOTAL				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	4.8	523.1	0.0
TOTAL				20,197	389	8,297	1,952	1,504	1,504	2.4	4.4	15	15	25,667	336	4.8	523	8,466

THOUVENOT, WADE & MOERCHEN, INC.
ENGINEERS ◆ SURVEYORS ◆ PLANNERS

TWM

☒ CORPORATE OFFICE
4940 OLD COLLINSVILLE RD.
SWANSEA, ILLINOIS 62226
TEL (618) 624-4488
FAX (618) 624-6688
corp@twm-inc.com

☐ EDWARDSVILLE OFFICE
1015B CENTURY DRIVE
EDWARDSVILLE, ILLINOIS 62025
TEL (618) 656-4040
FAX (618) 656-4343
edwardsville@twm-inc.com

☐ ST. LOUIS OFFICE
1001 CRAIG ROAD, SUITE 260
ST. LOUIS, MISSOURI 63146
TEL (314) 236-5052
FAX (314) 872-2194
stlouis@twm-inc.com

☐ WATERLOO OFFICE
113 SOUTH MAIN STREET
WATERLOO, ILLINOIS 62298
TEL (618) 939-5050
FAX (618) 939-3938
waterloo@twm-inc.com

PROFESSIONAL REGISTRATIONS	LICENSE NO.
ILLINOIS PROFESSIONAL DESIGN FIRM	184-001220
PROFESSIONAL ENGINEERING CORP.	62-035370
PROFESSIONAL STRUCTURAL ENGR. CORP.	81-005202
ILLINOIS PROF. LAND SURVEYING CORP.	048-000029
MISSOURI PROFESSIONAL ENGR. CORP.	NC 001528
MISSOURI LAND SURVEYING CORP.	NC 000346

SEAL

Signature:
Signature Date:
Expiration Date:

STATEMENT OF RESPONSIBILITY

I hereby confirm that the document herein to be authenticated by my seal is restricted to this sheet, and I hereby disclaim any responsibility for all other drawings, specifications, estimates, reports or other documents or instruments relating to or intended to be utilized for any other part of the architectural, engineering or survey project.

TITLE: SCHEDULE OF QUANTITIES

PROJECT: HUNTWOOD ROAD RECONSTRUCTION
VILLAGE OF SWANSEA
ST. CLAIR COUNTY

REV.	DATE	DESCRIPTION
△		
△		
△		

DRAWN BY:	BJG
DESIGNED BY:	BJG
CHECKED BY:	SJK
APPROVED BY:	SJK
PROJECT NUMBER	T20-030356

SHEET 12A OF 104 SHEETS

PROJECT DESCRIPTION: Huntwood Road ReConstruction

☒ ISSUED FOR REVIEW ☐ ISSUED FOR BIDDING
☐ ISSUED FOR CONSTR. ☐ RECORD DRAWING

P:\030356\dwg\Roadway Plans\ROADWAY PLANS\030356 SCHD.dwg 5/23/2008 7:40:07 AM CDT