



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 15, 2009

SUBJECT: FAU 9177 (Seibert Road)
Project M-5011(258)
Section 05-000007-03-PV & 06-00007-05-PV (Shiloh)
St. Clair County
Contract No. 97362
Item 172
April 24, 2009 Letting
Addendum (A)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Special provisions, page 6.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "DE" monogram.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation

COOPERATION WITH UTILITIES

The following companies have utility facilities within the limits of this project:

AT & T Telephone
AmerenIP
Illinois American Water
Charter Communications
Village of Shiloh

In addition to the requirements of Article 105.07 of the Standard Specifications, the Contractor shall coordinate his operations with the proposed utility adjustments to minimize delays in construction of the project.

The Contractor's attention is directed to the Status of Utilities contained elsewhere herein and the estimated completion dates for the various relocations and adjustments.

The Contractor shall coordinate his activities to allow for any inconvenience or delay caused by the adjustment of the water valves and telephone manholes which is expected to be on-going at the start of construction.

Compliance with this special provision shall be according to Article 105.07 of the Standard Specifications, and no additional compensation or remuneration will be allowed for any delays, inconvenience or damage sustained by the Contractor due to any interference from utility appurtenances or the operation of moving them, or on account of any special construction methods required in prosecuting the proposed work due to the existence of said appurtenances either in their present or relocated positions.

DISPOSAL OF SURPLUS MATERIALS

The Contractor shall be responsible for disposal of all surplus material which cannot be used for embankment. Surplus material that is suitable for embankment shall be segregated and stockpiled for use in the earth fill between the back of the curb and the right-of-way as shown on the cross sections.

The cost of this work shall be considered included in the cost of the individual removal pay items, and no additional payment will be allowed.

AGGREGATE SURFACE COURSE, TYPE B 6"

This shall be constructed according to the applicable portions of Section 402 of the Standard Specifications for Road and Bridge Construction and as directed by the Engineer except that this will be measured in square yards.

Payment for this item shall be at the contract unit price per square yard for AGGREGATE SURFACE COURSE, TYPE B 6" which price shall include all labor, equipment and material necessary and no additional compensation will be allowed.

Revised 4-15-09