

| F.A.P. RTE.         | SECTION      | COUNTY           | TOTAL SHEETS | SHEET NO. |
|---------------------|--------------|------------------|--------------|-----------|
| 312                 | 101-2(A,B,R) | ALEXANDER        | 152          | 6         |
| STA.                |              | TO STA.          |              |           |
| FED. ROAD DIST. NO. | ILLINOIS     | FED. AID PROJECT |              |           |

# SUMMARY OF QUANTITIES

|                         |                          |   |
|-------------------------|--------------------------|---|
| COUNTY:                 | ACF                      | ACNHF                                     |
| LOCATION:               | ALEXANDER RURAL          |   |
| ROUTE:                  | IL 146                   |   |
| FUNDING:                | 80% FEDERAL/ 20 % STATE  |   |
| WORK TYPE:              | ROADWAY                  | BOX CULVERT                               |
|                         | STA 2+539.4 TO STA 6+100 | PROPOSED SN 002-2002 EXISTING SN 002-0008 |
| CONSTRUCTION TYPE CODE: | I000-2A                  | X028-2A                                   |
|                         |                          | Y077                                      |

| CODE NUMBER | ITEM DESCRIPTION  | UNIT  | QUANTITY |          |         |
|-------------|---|-------|----------|----------|---------|
| M6021410    | MANHOLES, TYPE A, 1.2M DIAMETER, TYPE I FRAME, CLOSED LID         | EACH  | 1.0      | 1.0      |         |
| M6320030    | GUARDRAIL REMOVAL   | METER | 198.0    | 198.0    |         |
| M6320040    | CABLE ROAD GUARD REMOVAL  | METER | 165.0    | 165.0    |         |
| M6640100    | CHAIN LINK FENCE, 1.2 METER                                       | METER | 920.0    | 920.0    |         |
| M6650100    | WOVEN WIRE FENCE, 1.2 METER                                       | METER | 6,319.0  | 6,319.0  |         |
| M6650380    | WOVEN WIRE GATES, 1.2M X 7.3M DOUBLE                              | EACH  | 15.0     | 15.0     |         |
| M7030505    | PAVEMENT MARKING TAPE, TYPE III (SPECIAL)                         | METER | 1,616.0  | 1,616.0  |         |
| M7030620    | TEMPORARY PAINT PAVEMENT MARKING LINE 100MM                       | METER | 900.0    | 900.0    |         |
| M7031000    | WORK ZONE PAVEMENT MARKING REMOVAL                                | SQ M  | 60.0     | 60.0     |         |
| M7040100    | TEMPORARY CONCRETE BARRIER  | METER | 262.2    | 262.2    |         |
| * M7200100  | SIGN PANEL - TYPE 1   | SQ M  | 3.0      | 3.0      |         |
| * M7290100  | METAL POST - TYPE A   | METER | 52.0     | 52.0     |         |
| * M7800205  | PAINT PAVEMENT MARKING - LINE 100MM                               | METER | 900.0    | 900.0    |         |
| M7830100    | PAVEMENT MARKING REMOVAL  | SQ M  | 34.0     | 34.0     |         |
| MX032188    | CLASS SI CONCRETE, SPECIAL  | CU M  | 5.1      |          | 5.1     |
| MX032509    | GRADING AND SHAPING SPECIAL                                       | SQ M  | 1,428.0  | 1,428.0  |         |
| MX032842    | BOX CULVERT REMOVAL   | METER | 3.0      | 3.0      |         |
| MX033189    | WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL                      | LITER | 1,164.0  |          | 1,164.0 |
| MZ022800    | FENCE REMOVAL   | METER | 38.0     | 38.0     |         |
| * MZ054500  | ROCK FILL   | M TON | 26,957.0 | 26,957.0 |         |
| X0320547    | REMOVE AND REINSTALL END SECTION                                  | EACH  | 9.0      | 9.0      |         |
| X0322054    | REMOVAL OF PRECAST FLARED END SECTION                             | EACH  | 3.0      | 3.0      |         |
| XX004033    | CLEAN EXISTING CULVERTS   | EACH  | 6.0      | 6.0      |         |
| Z0007601    | BUILDING REMOVAL NO. 1  | L SUM | 1.0      | 1.0      |         |
| Z0007602    | BUILDING REMOVAL NO. 2  | L SUM | 1.0      | 1.0      |         |
| Z0007603    | BUILDING REMOVAL NO. 3  | L SUM | 1.0      | 1.0      |         |
| Z0007604    | BUILDING REMOVAL NO. 4  | L SUM | 1.0      | 1.0      |         |
| Z0013798    | CONSTRUCTION LAYOUT   | L SUM | 1.0      | 1.0      |         |
| Z0030250    | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3     | EACH  | 2.0      | 2.0      |         |
| ⊙ Z0076600  | TRAINEES  | HOUR  | 500.0    | 500.0    |         |
| A2C00G03    | TREE, DIOSPYROS VIRGINIANA (PERSIMMON), CONTAINER GROWN, 3-GALLON | EACH  | 116.0    |          | 116.0   |
| MX033760    | 50MMX200MMX1.2M PRESSURE TREATED LUMBER                           | EACH  | 3.0      |          | 3.0     |

\* SPECIALTY ITEMS  
⊙ Y080

|           |      |   |                            |
|-----------|------|---|----------------------------|
| REVISIONS |      | ILLINOIS DEPARTMENT OF TRANSPORTATION<br><br>SUMMARY OF QUANTITIES<br>3 OF 3<br><br>SCALE: VERT. / HORIZ.<br>DATE | DRAWN BY JCK<br>CHECKED BY |
| NAME      | DATE |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |
|           |      |   |                            |