CONTRACT NO. 98577

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(A,B,R)	ALEXANDER	152	17
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT

LOCATION STATION TO STATION	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N90	HOT-MIX ASPHALT BINDER COURSE IL-19.0, N90	SUB-BASE GRANULAR MATERIAL, TYPE A	POROUS GRANULAR EMBANKMENT	HOT-MIX ASPHALT SHOULDERS, 200MM	BITUMINOUS MATERIALS (PRIME COAT)
	M TON	M TON	M TON	CU M	SQ M	LITER
IL 146						
STA 5+687.5 TO STA 5+711.4	21.0	87.8	623.0		57.4	354.2
STA 5+500. TO STA 5+900. DETOUR ROAD		1,397.2				3,498.9
STA 5+521. TO STA 5+878. RIGHT SIDE OF DETOUR ROAD					211.4	306.5
STA 5+575. TO STA 5+825. LEFT SIDE OF DETOUR ROAD					314.2	455.4
STA 5+699.4 SIDES & TOP OF BOX CULVERT				836.0		
STA 5+699.40 FROM STRUCTURE PLANS (BELOW BOX)				103.0		
IL 146 PROJECT TOTAL	21.0	1,485.0	623.0	939.0	583.0	4,615.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 10/24/2008
FILE NAME = c:\pw_work\PWIDOT\KRANZJC\dms43642\d825qsch.n32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc