CONTRACT NO. 98577

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 312 | 101-2(A,B,R) | ALEXANDER | 152 | 19 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# DRAINAGE

| LOCATION | PIPE CULVERTS, CLASS A, TYPE 1 600 MM METER | PIPE CULVERTS, CLASS A, TYPE 1 750 MM METER | PIPE CULVERTS, CLASS A, TYPE 2 600 MM METER | PIPE CULVERTS, CLASS A, TYPE 2 750 MM METER | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM EACH | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 750MM EACH | CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 750MM EACH | PRECAST CONCRETE BOX CULVERT 900MM X 600MM MINIMUM FILL HEIGHT METER | PRECAST CONCRETE BOX CULVERT 900MM X 600MM AASHTO DESIGNATION | PRECAST CONCRETE BOX CULVERT 900MM X 600MM METER | REMOVE AND REINSTALL END SECTION FOR INFORMATION ONLY PRC FLARED END SECTION 750MM | REMOVE AND REINSTALL END SECTION FOR INFORMATION ONLY PRECAST END SECTION 900MM X 600MM | REMOVE AND REINSTALL END SECTION EACH | REMOVE AND RELAY PIPE CULVERTS 750MM METER | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546 EACH | FLUSH INLET BOX FOR MEDIAN, STANDARD 542546, SPECIAL EACH | INLET BOX, STANDARD 542531 EACH | MANHOLES, TYPE A, 1.2 DIA., TYPE 1 FRAME, CLOSED LID EACH | TRENCH BACKFILL CU M | CLEAN EXISTING CULVERTS EACH |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| IL 146 | | | | | | | | | | | | | | | | | | | | |
| WESTBOUND | | | | | | | | | | | | | | | | | | | | |
| STA 2+625.4 | | | | 3.0 | | | | | | | 1 | | 1 | | | | | | | |
| STA 2+839. | | | | | | | | | | | | | | | | | 1 | | | |
| STA 2+842.1 TO STA 2+844.5 | | | 2.4 | | | | | | | | | | | | | | | | | |
| STA 2+845.1 | | 25.0 | | | | | | | | | 1 | | 1 | | | | | 1 | 26.2 | |
| STA 3+320.3 | | | | 24.7 | | | | | | | 1 | | 1 | 2.3 | | 1 | | | 58.4 | |
| STA 3+844.3 | | | | 24.0 | | | | | | | 1 | | 1 | | | 1 | | | 34.1 | |
| STA 4+024.1 | | | | 27.0 | | | | | | | 1 | | 1 | 2.3 | | 1 | | | 72.0 | |
| STA 4+115.8 | | | | 25.7 | | | | | | | 1 | | 1 | 2.3 | | 1 | | | 73.3 | 1.0 |
| STA 4+274. | | | | 29.8 | | | 1 | | | | | | | 4.6 | | 1 | | | 96.2 | 1.0 |
| STA 4+689.6 | | | | 27.1 | | 1 | | | | | | | | | | 1 | | | 53.7 | 1.0 |
| STA 4+858.4 | | | | 25.0 | | | | | | | 1 | | 1 | | | 1 | | | 44.4 | 1.0 |
| STA 5+097.4 | | | | 27.3 | | 1 | | | | | | | | | | 1 | | | 52.8 | |
| STA 5+432.7 | | | | 26.9 | | | | | | | 1 | | 1 | | | 1 | | | 58.9 | 1.0 |
| STA 5+932.5 | | | | | | | | 1.2 | M 259 | 24.2 | | 1 | 1 | | | 1 | | | 49.9 | 1.0 |
| EASTBOUND | | | | | | | | | | | | | | | | | | | | |
| STA 13+100. | 23.0 | | | | 1 | | | | | | | | | | 1 | | | | 28.1 | |
| STA 13+500. | 23.0 | | | | 1 | | | | | | | | | | 1 | | | | 25.9 | |
| STA 13+725. | 22.9 | | | | 1 | | | | | | | | | | 1 | | | | 25.9 | |
| STA 14+499.22 | | | 25.4 | | 1 | | | | | | | | | | 1 | | | | 37.4 | |
| STA 15+274.19 | | | 23.3 | | 1 | | | | | | | | | | 1 | | | | 30.0 | |
| STA 15+624.19 | | | 27.0 | | 1 | | | | | | | | | | 1 | | | | 50.5 | |
| STA 15+775. | | | 24.0 | | 1 | | | | | | | | | | 1 | | | | 30.3 | |
| IL 146 PROJECT TOTALS | 68.9 | 25.0 | 102.1 | 240.5 | 7 | 2 | 1 | | | 24.2 | | | 9 | 11.5 | 7 | 10 | 1 | 1 | 848.0 | 6 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 10/24/2008
FILE NAME = c:\pw_work\PWIDOT\KRANZJC\dms43842\d02599mch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc