

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(A,B,R)	ALEXANDER	152	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ENTRANCE AND SIDE ROAD

LOCATION STATION TO STATION	WIDTH	EXISTING ENTRANCE INFORMATION		AGGEGATE SURFACE COURSE, TYPE A M TON	GRADING AND SHAPING SPECIAL SQ M	REMARKS
		TYPE	SURFACE			
IL 146						
RT STA 13+086.	6.6	FER	EARTH			
LT STA 3+086.	6.6	FEL	EARTH		190.7	
RT STA 13+220.		FER	EARTH			RELOCATE TO STA 13+086
LT STA 3+220.		FEL	EARTH		278.9	RELOCATE TO STA 3+086
LT STA 3+445.	5.0	PEL	AGGREGATE	22.5		
RT STA 13+445.	6.6	FER	EARTH			
RT STA 3+459.		FER	EARTH			RELOCATE TO STA 13+445
LT STA 3+575.	6.6	FEL	EARTH			
RT STA 13+575.		FER	EARTH			REMOVE
RT STA 13+787.	6.6	FER	EARTH			
RT STA 14+079. REIMAN RD	6.0	SRR	OIL & CHIP			
LT STA 4+079. GERARD RD	6.0	SRL	AGGREGATE			
LT STA 4+297.	3.6	PEL	AGGREGATE	23.5		
RT STA 14+301.	6.6	FER	EARTH			
RT STA 14+725.	6.6	FER	EARTH			
LT STA 4+717.	6.6	FEL	EARTH			
RT STA 14+900.	6.6	FER	EARTH			
LT STA 4+890.	6.6	FEL	EARTH			
RT STA 15+174.	6.6	FER	EARTH			
LT STA 5+175.	6.6	FEL	EARTH		261.6	
RT STA 15+270.		FER	EARTH			RELOCATE TO STA 15+174
LT STA 5+270.		FEL	EARTH		288.4	RELOCATE TO STA 5+175
RT STA 15+550.	6.6	FER	EARTH			
RT STA 15+570.		FER	EARTH			RELOCATE TO STA 15+550
LT STA 5+570.	6.6	FEL	EARTH		261.9	
LT STA 5+680.		FEL	EARTH		146.5	RELOCATE TO STA 5+570
RT STA 15+784.	6.6	FER	EARTH			
RT STA 15+804.		CER	AGGREGATE			RELOCATE TO STA 15+784
RT STA 15+944.1 CONIFER LN		CER	OIL & CHIP			REMOVE
IL 146 PROJECT TOTAL				46.0	1,428.0	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULE</p> <p>SCALE: VERT. DRAWN BY JCK HORIZ. CHECKED BY</p>

PLOT DATE = 10/24/2008
 FILE NAME = c:\p\work\p\DOT\VRANZ\IC\dra43642\402599.dwg
 PLOT SCALE = 50.0000 / IN.
 USER NAME = krenzj