

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	101-2(A,B,R)	ALEXANDER	152	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EROSION CONTROL

LOCATION STATION TO STATION	EROSION CONTROL BLANKET	HEAVY DUTY EXCELSIOR BLANKET	PERIMETER EROSION BARRIER	TEMPORARY DITCH CHECKS	INLET & PIPE PROTECTION
	SQ M	SQ M	METER	EACH	EACH
IL 146					
RT STA 14+684.				1.0	
RT STA 14+695.				1.0	
RT STA 14+710.				1.0	
RT STA 15+050.				1.0	
RT STA 15+095.				1.0	
RT STA 15+185.				1.0	
RT STA 15+365.				1.0	
RT STA 15+645.				1.0	
RT STA 15+657.				1.0	
RT STA 15+695.				1.0	
RT STA 15+705.				1.0	
RT STA 15+720.				1.0	
RT STA 15+735.				1.0	
RT STA 15+975.				1.0	
LT STA 12+965.				1.0	
LT STA 13+055.				1.0	
LT STA 13+110.				1.0	
LT STA 13+290.				1.0	
LT STA 13+325.				1.0	
LT STA 13+520.				1.0	
LT STA 13+705.				1.0	
LT STA 13+860.				1.0	
LT STA 14+310.				1.0	
LT STA 14+490.				1.0	
LT STA 15+040.				1.0	
LT STA 15+985.				1.0	
LT STA 0+000.			TURN RAMP	1.0	
LT STA 0+090.			TURN RAMP	1.0	
RT STA 12+550. TO STA 12+625.	225.0				
RT STA 12+625. TO STA 12+675.		150.0			
RT STA 12+675. TO STA 12+825.	450.0				
RT STA 12+825. TO STA 12+845.		60.0			
RT STA 12+845. TO STA 13+204.	1,077.0				
RT STA 13+310. TO STA 13+925.	1,845.0				
RT STA 13+925. TO STA 14+047.		366.0			
RT STA 14+100. TO STA 14+126.		78.0			
RT STA 14+126. TO STA 14+296.	510.0				
RT STA 14+296. TO STA 14+325.		87.0			
RT STA 14+325. TO STA 14+682.	1,071.0				
RT STA 14+682. TO STA 14+725.		129.0			
RT STA 14+725. TO STA 14+750.		75.0			
RT STA 14+857. TO STA 14+900.		129.0			
RT STA 14+900. TO STA 15+475.	1,725.0				
RT STA 15+525. TO STA 15+700.	525.0				
RT STA 15+700. TO STA 15+750.		150.0			
RT STA 15+750. TO STA 15+830.	240.0				
RT STA 15+931. TO STA 16+075.	432.0				
LT STA 5+925. TO STA 6+006.	243.0				
LT STA 0+000. TO STA 0+133.	399.0				
STA 2+636.3 TO STA 2+831.		1,207.0			
STA 2+831. TO STA 3+445.		6,140.0			
STA 3+445. TO STA 4+079.		6,340.0			
STA 4+079. TO STA 5+175.		10,960.0			
STA 5+175. TO STA 5+700.		5,250.0			
STA 5+700. TO STA 6+089.		3,890.0			
RT STA 15+702. TO STA 15+932.		82.0	WETLAND		
IL 146 PROJECT TOTALS	42,529.0	1,306.0	439.0	67.0	18.0

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE SCALE: VERT. HORIZ. DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 11/25/2008
 FILE NAME = c:\pwworkspace\p1\101101101\101101101\101101101.dwg
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = kranzjg