CONTRACT NO. 98577

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 312 | 101-2(A,B,R) | ALEXANDER | 152 | 105 |
| STA. 3+320.21 | | TO STA. 3+350.00 | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |

℄ WBL

℄ EBL

EXIST ROW
22.787 M LT

102.742

101.536
102.824

1:6.2

1:6.2

101.900

EARTHWORK AHEAD: CUT = 9.5 FILL = 8.4
UNSTABLE SOIL CUT = 2.2 ROCK FILL = 10.9
EARTHWORK BACK: CUT = 9.5 FILL = 20.9

STA 3+350
REMOVAL OF UNSTABLE SOILS BEGINS

1:6

1:4

1:3

99.913

PROP ROW
54.843 M RT

3+350.00

EXIST ROW
22.789 M LT

102.735

100.537
102.824

1:5.3

1:5.3

101.837

CUT = 1.8 FILL = 45.6

1:6

1:4

1:3

99.760

PROP ROW
54.843 M RT

3+325.00

EXIST ROW
22.789 M LT

102.734

100.055
102.824

1:4.9

1:4.9

101.763

1:6

1:4

99.701

1:3

99.700

99.707

99.701

CUT = 0.8 FILL = 56.1

EXISTING 760MM RCCP EXTENSION
REMOVE EXISTING END SECTION AND 2.7M OF EXISTING PIPE
PIPE CULVERT REMOVAL, 0.4M
REMOVE AND RELAY PIPE CULVERTS, 2.3M
FLUSH INLET BOX FOR MEDIAN, STANDARD 542546, SPECIAL, 1 EACH
PIPE CULVERTS, CLASS A, TYPE 2 750MM: 24.7M
REMOVE AND REINSTALL END SECTION, 1 EACH

3+320.21

IL 146: STA 3+320.21 TO STA 3+350.00

| FINAL SURVEY NOTE: ROCK | SURVEYED BY: DATE: |
|---|---|
| NO. | AREAS CHECKED |

| ORIGINAL SURVEY | BY | DATE |
|---|---|---|

PLOT DATE = 10/27/2020
FILE NAME = c:\projects\ydot\ief\ewchdl\dsn\e255sur-R14ortsm02
PLOT SCALE = 100.0000 m / M.
USER NAME = ief\ewchdl