

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	JACKSON	23	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING SCHEDULE

• (12-3)RS-2,(4-5)RS-3

STATION TO STATION	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID						PREFORMED PLASTIC PAVEMENT MARKING, TYPE B	TEMPORARY					NOTES		
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH	6 INCH WHITE	12 INCH WHITE	24 INCH WHITE	LETTERS & SYMBOLS WHITE	4 INCH	6 INCH	12 INCH	24 INCH	LETTERS & SYMBOLS			
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	SQ FT			
MAINLINE: Sta. 100+37 to Sta. 184+75															
	100+37.0	TO	127+69.7												
	127+69.7	TO	134+52.0												
Railroad Crossing at Sta. 134+52 to Sta. 134+91															
	134+91.0	TO	156+60.0												
	156+60.0	TO	181+00.0												
	181+00.0	TO	182+66.0												
	182+66.0	TO	184+65.0												
Left	128+03.0	TO	132+03.0	400.0									Turn Lane Line		
Left	182+66.0	TO	184+65.0	199.0									Turn Lane Line		
Right	176+40.0	TO	178+50.0	420.0									Old IL 13 Connector		
	115+09.0														
	116+49.0														
	116+49.0														
	117+14.0														
	117+20.0														
	117+68.0														
	127+27.0														
LEFT	127+48.0	TO	127+92.0												
	127+33.0														
	1279+87.0														
LEFT	128+23.0														
LEFT	128+51.0														
LEFT	131+47.0														
LEFT	131+75.0														
	132+03.0														
	132+03.0														
RIGHT	132+17.0	TO	132+67.0												
RIGHT	132+39.0														
RIGHT	132+41.0	TO	132+80.0	48.0											
RIGHT	132+45.0														
RIGHT	132+50.0														
RIGHT	132+57.0														
	132+63.0														
	133+11.0														
	133+58.0														
	133+58.0														
	133+61.0														
	134+36.0														
	136+60.0														
	136+66.0														
	137+26.0														
	142+48.0														
	143+04.0														
	155+42.0														
	155+48.0														
LEFT	184+00.0														
LEFT	184+28.0														
LEFT	184+28.0														
	184+60.0														
MAINLINE SUB-TOTALS				1,115	0	4,245	1197	220	359	409.4	5360	1197	220	359	409.4
PARKING LANE: LT. STA. 125+77 TO LT. STA. 127+27															
LEFT	102+31														
LEFT	105+47														
LEFT	125+77.0	TO	125+37.0												
LEFT	125+37.0	TO	126+86.0	24.0											
LEFT	127+27.0														
PARKING LANE SUB-TOTALS				24.0	109.0	0	0.0	0.0	0.0	0.0	133	0	0	0	0.0
SUB-TOTALS				1,139.0	109.0	4,244.5	1,197.0	220.0	359.0	409.4	5493	1197.0	220.0	359.0	409.4
TOTALS				5,493			1,197.0	220.0	359	409.4	5493	1,197	220	359	409.4

PLOT DATE = 12/1/2008
 FILE NAME = c:\pva\work\mason\mason.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = mason