CO056

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	298	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	1,834	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,464	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	1,893	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	267	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	532	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	14,784	
AR501509	9" PCC PAVEMENT	S.Y.	267	
AR501911	REMOVE AND REPLACE PCC PAVEMENT	S.F.	25	
AR510511	TIE DOWN-TYPE A	EACH	29	
AR510512	TIE DOWN-TYPE B	EACH	31	
AR510515	GROUND ROD	EACH	1	
AR510901	REMOVE TIE DOWN-TYPE A	EACH	29	
AR510902	REMOVE TIE DOWN-TYPE B	EACH	29	
AR603510	BITUMINOUS TACK COAT	GAL.	7,704	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	1,937	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	2,114	
AR625510	TAR EMULSION SEAL COAT	S.Y.	1,986	
AR751940	ADJUST INLET	EACH	1	
AR904510	SODDING	S.Y.	298	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED CONSTRUCTION PLAN STA. 28+62.8 TO STA. 31+00
5	PROPOSED CONSTRUCTION PLAN STA. 31+00 TO STA. 33+43
6	PROPOSED PAVEMENT PREPARATION PLAN STA. 28+62.8 TO 31+00
7	PROPOSED PAVEMENT PREPARATION PLAN STA. 31+00 TO 33+43
8	PROPOSED TIE DOWN REMOVAL PLAN STA. 28+62.8 TO 31+00
9	PROPOSED TIE DOWN REMOVAL PLAN STA. 31+00 TO 33+43
10	PROPOSED STAKING PLAN STA. 28+62.8 TO 31+00
11	PROPOSED STAKING PLAN STA. 31+00 TO 33+43
12	PROPOSED PCC PAVEMENT PLAN
13	PROPOSED TIE DOWN PLAN STA. 28+62.8 TO 31+00
14	PROPOSED TIE DOWN PLAN STA. 31+00 TO 33+43
15	PROPOSED MARKING PLAN STA. 28+62.8 TO 31+00
16	PROPOSED MARKING PLAN STA. 31+00 TO 33+43
17	PROPOSED CROSS-SECTIONS STA. 28+62.8 TO STA. 28+75
18	PROPOSED CROSS-SECTIONS STA. 29+00 TO STA. 29+25
19	PROPOSED CROSS-SECTIONS STA. 29+50 TO STA. 29+75
20	PROPOSED CROSS-SECTIONS STA. 30+00 TO STA. 30+26.24
21	PROPOSED CROSS-SECTIONS STA. 30+50 TO STA. 30+60
22	PROPOSED CROSS-SECTIONS STA. 30+75 TO STA. 31+00
23	PROPOSED CROSS-SECTIONS STA. 31+25 TO STA. 31+50
24	PROPOSED CROSS-SECTIONS STA. 31+75 TO STA. 32+00
25	PROPOSED CROSS-SECTIONS STA. 32+25 TO STA. 32+50
26	PROPOSED CROSS-SECTIONS STA. 32+75 TO STA. 33+00
27	PROPOSED CROSS-SECTIONS STA. 33+25 TO STA. 33+43

DATE	REVISION	BY
4/02/09	REVISED AS PER IDA REVIEW COM	CAH

COLES COUNTY AIRPORT AUTHORITY

IL. PROJ.: MTO-3856 A.I.P. PROJ.: 3-17-0066-B23

Hanson Project No.	08A01980 0800
Filename	R-002FLP.DWG
Scale	NOT TO SCALE
Date	11/18/08

LAYOUT	CAH	11/18/08
DRAWN	BAK	11/18/08
REVIEWED	CAH	03/13/09

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

REHABILITATE CENTER APRON

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

2

APR 02, 2009 7:09 AM HAGLOND3W2
J:\PROJECTS\COLES\08A01980\AIRPORT\SHEETS\R-002FLP.DWG - Layout1