


# RECONSTRUCTION OF RUNWAY END 35

SUMMARY OF QUANTITIES				
ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR107408	L-806 WIND CONE 8' LIGHTED	EACH	2	
AR107900	REMOVE WIND CONE	EACH	2	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	5,427	
AR109210	VAULT MODIFICATIONS	L.S.	1	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	56	
AR125410	MITL - STAKE MOUNTED	EACH	23	
AR125415	MITL - BASE MOUNTED	EACH	3	
AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	2	
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	3	
AR125505	MIRL, STAKE MOUNTED	EACH	2	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	6	
AR125545	MI THRESHOLD LIGHT BASE MTD	EACH	2	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	16	
AR125965	RELOCATE RWY DISTANCE REMAIN SIGN	EACH	5	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	5,331	
AR156511	DITCH CHECK	EACH	1	
AR156520	INLET PROTECTION	EACH	2	
AR156530	TEMPORARY SEEDING	ACRE	4.1	
AR156540	RIPRAP	S.Y.	22	
AR201610	BITUMINOUS BASE COURSE	TON	2,143	
AR208540	OVERSIZED AGGREGATE	TON	2,558	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	2,716	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,286	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	900	
AR602510	BITUMINOUS PRIME COAT	GAL.	2,535	
AR603510	BITUMINOUS TACK COAT	GAL.	2,143	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	62,965	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	31,965	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	26,705	
AR701515	15" RCP, CLASS IV	L.F.	156	
AR701518	18" RCP, CLASS IV	L.F.	147	
AR705410	POROUS BACKFILL	C.Y.	53	
AR705526	6" PERFORATED UNDERDRAIN W/SOCK	L.F.	2,133	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	8	
AR705900	REMOVE UNDERDRAIN	L.F.	477	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	4	
AR751411	INLET-TYPE A	EACH	2	
AR752418	PRECAST REINFORCED CONC. FES 18"	EACH	1	
AR901510	SEEDING	ACRE	4.1	
AR904510	SODDING	S.Y.	641	
AR908510	MULCHING	ACRE	3.9	

DATE	REVISION	BY

ST. LOUIS REGIONAL AIRPORT  
  
 EAST ALTON, ILLINOIS  
 I.L. PROJ.: AIN-3825 A.I.P. PROJ.: 3-17-0002-B42

HS Project No.: 83706RWYD-0800	02/07/08
Program: R-004FLP.DWG	02/07/08
Scale: N/A	02/07/08
Date: 02/07/08	07/11/08
LAYOUT	MDR
DRAWN	MDR
REVIEWED	CAH

**HANSON**  
  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2886  
 Offices Nationwide

RUNWAY SAFETY  
 AREA IMPROVEMENTS  
 SUMMARY OF QUANTITIES  
 FOR  
 RUNWAY END 35