



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2015

SUBJECT: FAU Route 2792 (Lawndale Avenue)
Section 12-00018-00-RS (McCook)
Cook County
Contract No. 61B15
Item 126
April 24, 2015 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Deleted the Special Provision HMA-Quantity Correction (BMPP) from page 17**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

INDEX OF SPECIAL PROVISIONS

STATE OF ILLINOIS 1

SPECIAL PROVISIONS 1

LOCATION OF PROJECT 1

DESCRIPTION OF PROJECT 1

MAINTENANCE OF ROADWAYS 1

STATUS OF UTILITIES TO BE ADJUSTED 2

TRAFFIC CONTROL PLAN 4

FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)..... 5

TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR6
INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS 6

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT..... 10

ADJUSTMENTS AND RECONSTRUCTIONS..... 12

DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1)..... 13

GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1)..... 15

~~HOT MIX ASPHALT - QUANTITY CORRECTION (BMIPR)..... 17~~

HMA MIXTURE DESIGN REQUIREMENTS (D-1) 18

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1)..... 34

~~NOT MIX ASPHALT QUANTITY CORRECTION (BMPR)~~

~~Effective: October 1, 2014
Revised: October 2, 2014~~

Revise the fifth paragraph of Article 406.13(b) of the Standard Specifications to read as follows:

"HMA and Stone Matrix Asphalt (SMA) mixture in excess of 103 percent of the quantity shown on the plans or the plan quantity as specified by the Engineer will not be measured for payment. The "adjusted quantity to be placed" and the "adjusted pay quantity" for HMA and SMA mixtures will be calculated as follows.

Adjusted Quantity To Be Placed = C x quantity shown on the plans or the plan quantity as specified by the Engineer

where: C = English: $C = \frac{G_{mb} \times 46.8}{U}$ Metric: $C = \frac{G_{mb} \times 24.99}{U}$

and where: G_{mb} = average bulk specific gravity from approved mix design
U = unit weight of HMA shown on the plans in lb/sq yd/in.
(kg/sq m/25 mm), used to estimate plan quantity
46.8 = English constant
24.99 = metric constant

Adjusted Pay Quantity (not to exceed 103 percent of the quantity shown on the plans or the plan quantity as specified by the Engineer) = B x HMA tons actually placed

where: $B = \frac{1}{C}$

If project circumstances warrant a new mix design, the above equations shall be used to calculate the adjusted plan quantity and adjusted pay quantity for each mix design using its respective average bulk specific gravity."