



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 14, 2015

SUBJECT: FAU Route 1409 (Crescent Boulevard)
Section 12-00076-00-PV (Glen Ellyn)
DuPage County
Contract No. 61B09
Item 172
April 24, 2015 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

- 1. Deleted the Special Provision HMA-Quantity Correction (BMPP) from page 38**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.
Engineer of Project Management

INDEX OF SPECIAL PROVISIONS

LOCATION OF IMPROVEMENTS.....	1
DESCRIPTION OF IMPROVEMENTS.....	1
MAINTENANCE OF ROADWAYS.....	1
COMPLETION DATE PLUS WORKING DAYS.....	2
STATUS OF UTILITIES TO BE ADJUSTED	2
PUBLIC CONVENIENCE AND SAFETY (DIST 1)	4
PRE-CONSTRUCTION VIDEO LOG.....	4
COARSE AGGREGATE FOR BACKFILL, TRENCH BACKFILL AND BEDDING (D-1)	5
AGGREGATE SUBGRADE IMPROVEMENT (D-1).....	5
PCC PAVEMENT , SPECIAL.....	8
SLIPFORM PAVING (D-1).....	8
CALCIUM ALUMINATE CEMENT (BMPR)	8
HEAT OF HYDRATION CONTROL FOR CONCRETE STRUCTURES (D-1).....	9
HMA MIXTURE DESIGN REQUIREMENTS (D-1)	9
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (D-1).....	26
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1).....	36
HOT MIX ASPHALT - QUANTITY CORRECTION (BMPR).....	38
DETECTABLE WARNINGS FOR SIDEWALK RAMPS	39
FENCE REMOVAL	39
REMOVE EXISTING PARKING BLOCKS.....	40
DELINEATOR REMOVAL.....	40
TIMBER RETAINING WALL REMOVAL	41

Revised 4-14-15

"(c) RAP Materials (Note 3)1031"

Add the following note to 1030.02 of the Standard Specifications:

Note 3. When using reclaimed asphalt pavement and/or reclaimed asphalt shingles, the maximum asphalt binder replacement percentage shall be according to the most recent special provision for recycled materials.

~~HOT MIX ASPHALT - QUANTITY CORRECTION (BMPI)~~

~~Effective: October 1, 2014~~

~~Revised: October 2, 2014~~

Revise the fifth paragraph of Article 406.13(b) of the Standard Specifications to read as follows:

"HMA and Stone Matrix Asphalt (SMA) mixture in excess of 103 percent of the quantity shown on the plans or the plan quantity as specified by the Engineer will not be measured for payment. The "adjusted quantity to be placed" and the "adjusted pay quantity" for HMA and SMA mixtures will be calculated as follows.

Adjusted Quantity To Be Placed = C x quantity shown on the plans or the plan quantity as specified by the Engineer

where: C = English: $C = \frac{G_{mb} \times 46.8}{U}$ Metric: $C = \frac{G_{mb} \times 24.99}{U}$

and where: G_{mb} = average bulk specific gravity from approved mix design
U = unit weight of HMA shown on the plans in lb/sq yd/in.
(kg/sq m/25 mm), used to estimate plan quantity
46.8 = English constant
24.99 = metric constant

Adjusted Pay Quantity (not to exceed 103 percent of the quantity shown on the plans or the plan quantity as specified by the Engineer) = B x HMA tons actually placed

where: $B = \frac{1}{C}$

If project circumstances warrant a new mix design, the above equations shall be used to calculate the adjusted plan quantity and adjusted pay quantity for each mix design using its respective average bulk specific gravity."