



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 15, 2020

SUBJECT: Wolf Creek State Park Internal Park Roads  
Section WOLF CREEK 2019  
Shelby County  
Contract No. 46907  
Item No. 140, April 24, 2020 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 7 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

## **INFORMATION KIOSK COMPLETE**

Description – This work shall consist of furnishing, fabricating, and installing kiosk, hardware and related items in accordance with the details and at the locations noted in the plans.

Roofing shall be 24 gauged ribbed galvalume steel sheets and painted with Kynar 500 to IDNR's specified color. Minimum clearance height under the structure shall be 7.5'. Steel columns shall be hollow structural steel tube minimum ASTM A500 grade B with a minimum wall thickness of 3/16". Structural framing shall be hollow structural steel tube minimum ASTM A500 grade B, "I" beams. Frame color shall be determined by IDNR prior manufacturing of kiosk. Install all components according to manufacturer's installation instructions and these specifications. Kiosk shall have a lockable enclosed double sided display case attached between the two structure support columns. Kiosk shall have a 10 year limited warranty. Acceptable manufacturer shall be Poligon, a product of Porter Corp., Model #SSG 8x9 with double sided display case; or an approved equivalent.

Removal of the existing information kiosk and concrete pad shall be included in the cost of the new information kiosk. Grading that is needed to maintain drainage away from center of kiosk including topsoil placement, seeding, and fertilizer shall be considered included in this pay item.

Basis of Payment – This work will be paid for at the contract unit price per each for INFORMATION KIOSK COMPLETE.

## **MINOR SIGN COMPLETE**

Description – This work shall consist of furnishing and installing signs, posts, framing, hardware and related items in accordance with the details and at the locations noted in the plans and in accordance with Sections 720 and 730 of the Standard Specifications.

The sign members shall be fiberglass reinforced recycled plastic. The color for the timber and signs shall be submitted to the IDNR Project Manager for approval prior to fabrication. The sign post shall be constructed in accordance with Section 728 of the Standard Specifications. The sign panels shall be supplied by the manufacturer in accordance with the details in the plans and the Standard Specifications. This item shall also include the removal and disposal of the existing camp site signs.

**If the contractor wishes to use another material for these signs, including HDPE, a sample of the material must be submitted to the Engineer for IDNR approval prior to use.**

Basis of Payment – This work will be paid for at the contract unit price per each for MINOR SIGN COMPLETE.

## **SIGN AND POST**

Description – This work shall consist of furnishing and installing signs, posts, framing, hardware and related items in accordance with the details and at the locations noted in the plans and in accordance with Sections 720 and 729 of the Standard Specifications.

Revised April 15, 2020