



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 9, 2020

SUBJECT: FAU 8994 (State Street)
Section 16-00238-00-RS (Alton)
Madison County
Contract No. 97725
Item 191
April 24, 2020 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 12 of the special provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

The Contractor shall use high-early strength concrete in these areas to meet the maximum closures allowed. No additional compensation will be allowed for high-early concrete.

If the Contractor wishes to deviate from the traffic control and protection established by this Special Provision, he shall provide a revised traffic control plan in writing for the review and approval of the Engineer.

Payment for this work shall be made at the contract lump sum price for ~~TRAFFIC CONTROL AND PROTECTION (SPECIAL)~~.

TEMPORARY PAVEMENT MARKING REMOVAL

~~This work consists of removing temporary pavement markings, if temporary pavement markings are required by the project.~~

~~This work shall be done in accordance with Section 783 of the Standard Specifications.~~

~~Water blasting shall be the method used.~~

~~Payment for this work shall be made at the contract unit price per square foot for TEMPORARY PAVEMENT MARKING REMOVAL.~~

PAINT CURB

This work shall be done in accordance with Section 780 of the Standard Specifications.

The face of curb and 6 inches of the top of the curb shall be painted at the locations shown on the plans.

Payment for this work shall be made at the contract unit price per foot for PAINT CURB.

HANDHOLE, COMPOSITE CONCRETE (SPECIAL)

This work consists of furnishing and installing a composite concrete handhole.

This work shall be done in accordance with Section 814 of the Standard Specifications and as herein specified.

The new composite handholes shall be placed at the exact elevations, running slopes and cross slopes to match the proposed sidewalk curb ramp designs shown in the plans. The handholes shall also be placed to accommodate the existing conduits.

Payment for this work shall be made at the contract unit price per each for HANDHOLE, COMPOSITE CONCRETE (SPECIAL).

DETECTOR LOOP REPLACEMENT

This work consists of replacing existing traffic signal detector loops that conflict with the work of this project or that no longer function.