

CONTRACT NO. 60004

F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
305	2007-028 RS	COOK	35	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	TRAFFIC SIGNALS Y031-1F	SFTY-2A 016-0535			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	106	106					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	24	24					
40600300	AGGREGATE (PRIME COAT)	TON	116	116					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	9					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	210	210					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	395	395					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2825	2825					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	28800	28800					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	85	85					
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SO YD	1392	1392					
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SO FT	292.5	292.5					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	1200	1200					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	112	112					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	80	80					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1150	1150					
50102400	CONCRETE REMOVAL	CU YD	22.9			22.9			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	22.9			22.9			
50300300	PROTECTIVE COAT	SO YD	62			62			
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	38	38					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	10	10					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	33	33					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	0.8	0.1	0.1			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000	TRAFFIC SIGNALS Y031-1F	SFTY-2A 016-0535			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5		0.5			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	0.5		0.5			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5000	5000					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	454.3	454.3					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	26200	26200					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2000	2000					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	480	480					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	450	450					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	454.3	454.3					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26200	26200					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	480	480					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	450	450					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	290	290					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	290	290					
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	90		90				
* 81400100	HANDHOLE	EACH	1		1				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	1		1				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4		4				
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	575		575				

2/7/2008 10:42:30 AM c:\work\60004\60004.dwg

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

\* SPECIALTY ITEMS

Rev.